

ELECTRICAL SERVICE - PANEL DIAGRAM (TYPICAL FOR POLE AND GROUND MOUNTED SERVICE)


SERVICE INSTALLATION POLE MOUNT (SHOWN) 13.75" (0.35 m) DOOR OPENING I.D.O.T. IDENTIFICATION DECALS SHALL BE MOUNTED TO FRONT OF BOORS OF ALL TYPES ELECTRIC 10' (3.0m) MAX. UTILITY DOOR-ENCLOSURE -ELECTRICAL SERVICE LOCK (ABOVE OR BELOW SEE PANEL DIAGRAM, ABOVE 13.75" (0.35m) GROUND) CONDUIT BUSHINGS - SEE CABINET BASE, BELOW 1" CHAMFER, CONTINUOUS SEE ELECTRICAL FINISH GRADE-SERVICE 24" (0,60m), - 4" (1.2m) DEPTH PANEL DIAGRAM-TO TRAFFIC SIGNAL CONTROLLER 2" (50mm) GALV. CONDUIT 2" (50mm) GALV. CONDUIT _________ SERVICE INSTALLATION -3/4" x 10' (20mm x 3.0m) COPPER CLAD GROUND ROD **GROUND MOUNT** (413 mm) 16.25" (0.29 m) 11.50" CABINET BASE-1.44" (37 mm)


CABINET - BASE BOLT PATTERN (NOT TO SCALE)

-ANCHOR


BOLT LOCATIONS

(29 mm)





DETAIL "B"



HANDHOLE COVER & FRAME - GROUNDING DETAIL

(2) $1/2'' \times 1$ 1/4'' STAINLESS STEEL BOLT WITH SPLIT LOCK WASHER AND NYLON INSERT LOCKOUT WELDED TO -7FRAME AND TO COVER, (TYPICAL) HEAVY DUTY COPPER COMPRESSION GROUNDING TERMINAL. (TYPICAL) EXISTING HANDHOLE (PAID FOR SEPARATELY) FRAME AND COVER

EXISTING HANDHOLE COVER & FRAME - GROUNDING DETAIL


(NOT TO SCALE)


NOTES:

GROUNDING SYSTEM

RTE. SECTION COUNTY TOTAL SHEE SHEETS NO. 3545 54 WRS-7 DUPAGE 235 127 STA. TO STA FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT D-91-386-01 CONTRACT NO. 6229

- 1. THE GROUNDING SYSTEM SHALL CONSIST OF AN INSULATED CONDUCTOR TYPE XLP, NO. 6 A.W.G., STRANDED COPPER TO BE INSTALLED IN RACEWAYS. THE GROUNDING CABLE SHALL BE INSTALLED IN A CONTINUOUS MANNER AS SHOWN ON THE CABLE PLAN PROVIDED. ALL GROUNDING CONDUCTORS SHALL BE BONDED TO METAL ENCLOSURE (HANDHOLE, POST, MAST ARM, CONTROLLER, ETC.). GROUND ROD SHALL BE 3/4" DIA, x 10'-0" (20mm x 3.0m) LONG, COPPER CLAD, ONE GROUND ROD SHALL BE INSTALLED AT ALL POST FOUNDATIONS, POLE FOUNDATIONS, CONTROLLER CABINET FOUNDATION AND ELECTRICAL SERVICE INSTALLATION AS INDICATED ON THE CABLE PLAN. IF THERE ARE ANY SPECIAL CONDITIONS SUCH AS SUB-SURFACE CONDITIONS OR INSTALLATION PROBLEMS, THE RESIDENT ENGINEER SHALL BE NOTIFIED OR CONTACT THE BUREAU OF TRAFFIC, ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT ONE AT (847) 705-4139-
- 2. THE NEUTRAL CONDUCTOR AND THE GROUND CONDUCTOR SHALL BE CONNECTED IN THE SERVICE INSTALLATION. AT NO OTHER POINT IN THE TRAFFIC SIGNAL SYSTEM SHALL THE NEUTRAL AND GROUND CONDUCTORS BE CONNECTED.
- 3. ALL EQUIPMENT GROUNDING CONDUCTORS SHALL TERMINATE AT THE GROUND BUS IN THE CONTROLLER CABINET.
- 4. THE CONTRACTOR SHALL PROVIDE A GROUND CABLE WITH CONNECTORS BETWEEN THE HANDHOLE COVER AND HANDHOLE FRAME.








3/4" (20mm) HEAVY-DUTY GROUND ROD CLAMP (BURNDY TYPE GRC OR APPROVED EUAL)

- ALL CLAMPS SHALL BE BRONZE OR COPPER, UL APPROVED.
 GROUND CABLE SHALL BE LOOPED OVER HOOKS IN THE HANDHOLES
- 6.5' (2.0m) SLACK SHALL BE PROVIDED IN SINGLE HANDHOLES 13' (4.0m) OF SLACK SHALL BE PROVIDED IN DOUBLE HANDHOLES. 5' (1.4m) OF SLACK SHALL BE PROVIDED BETWEEN FRAME AND COVER.



ILLINOIS DEPARTMENT OF TRANSPORTATION DISTRICT 1 STANDARD TRAFFIC SIGNAL DESIGN DETAILS

SCALE: VERT. NONE HORIZ. NONE DATE 1-01-02