



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 10, 2005

SUBJECT: FAI Route 94

Project IM-NHI-094-3(393) 060

Section (1516.1, 1717 & 1818) R-9

Cook County

Contract No. 62695

Item No. 160, June 17, 2004 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page vii of the Table of Contents.
2. Revised pages 3 and 4 of the Special Provisions.
3. Added pages 429 and 430 to the Special Provisions.
4. Revisd pages 1 – 5, 7, 9, 13 – 15, 20 and 25 – 27 of the Schedule of Prices.
5. Revised sheets 11, 12, 14, 16, 17 – 19, 21, 22, 36 – 38, 41, 103, 104, 110, 114, 116, 118, 119, 121, 123, 125, 128 – 130, 213, 213A, 216, 248, 259, 260, 264 – 266, 368, 370, 372, 377, 421, 423 and 672 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by a small 'P.E.' monogram.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; N. R. Stoner; Roger Driskell; R. E. Anderson; Jim White; Design & Environment File

TBW:TK:jc

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)	388
SHOULDER STABILIZATION AT GUARDRAIL (BDE)	390
STABILIZED SUBBASE AND BITUMINOUS SHOULDERS SUPERPAVE (BDE)	390
SUBGRADE PREPARATION (BDE)	396
SUPERPAVE BITUMINOUS CONCRETE MIXTURE IL-4.75 (BDE)	396
SUPERPAVE BITUMINOUS CONCRETE MIXTURES (BDE)	400
SURFACE TESTING OF PAVEMENTS (BDE)	406
SUSPENSION OF SLIPFORMED PARAPETS (BDE)	413
TEMPORARY CONCRETE BARRIER (BDE)	413
TRAFFIC BARRIER TERMINALS (BDE)	415
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE)	416
TRAINING SPECIAL PROVISIONS	416
TRANSIENT VOLTAGE SURGE SUPPRESSION (BDE)	419
TRUCK BED RELEASE AGENT (BDE)	420
WEIGHT CONTROL DEFICIENCY DEDUCTION	420
WORK ZONE PUBLIC INFORMATION SIGNS (BDE)	422
WORK ZONE SPEED LIMIT SIGNS (BDE)	422
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	423
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	424
STEEL COST ADJUSTMENT (BDE)	424
USE OF MULTIPLE PLANTS IN THE SAME CONSTRUCTION ITEM	429
ILLINOIS ON-THE-JOB TRAINING	430

Revised 06-10-2005

STATUS OF UTILITIES TO BE ADJUSTED

Effective: January 30, 1987


Revised: July 1, 1994

Utility companies involved in this project have provided the estimated dates:

<u>Name of Utility</u>	<u>Type</u>	<u>Location</u>	<u>Estimated Dates for Start and Completion of Relocation or Adjustments</u>
Peoples Energy	24" Gas	76 th St. Bridge, Along State Street	No conflict anticipated. Hand excavation is required. Contact Mr. Ed Proctor at 773-962-4840 at least 48 hours in advance. Emergency Number 312-240-7001
Peoples Energy	1- 16" L.P. Steel, 16" M.P. Steel Both mains in potential conflict with retaining wall and slope grading.	79 th St Two locations. Station 1313+40 STATION 1313+45	No conflict anticipated. Hand excavation is <u>required</u> for corner garden installation. Contact Mr. Ed Proctor at 773-962-4840 at least 48 hours in advance. Emergency Number 312-240-7001
SBC	36 MTD in potential conflict with retaining wall and ramp grading	77 th St Station 1325+92	SBC to lower in place. Adjustment completed by September 1, 2005.
SBC	18 MTD in potential conflict with retaining wall and ramp grading.	Near 92 nd St. Station 1226+79	SBC to lower duct in place through side slope area. Adjustment completed by September 1, 2005.
SBC	12 MTD in potential conflict with retaining wall and side slope grading.	95 th Street Station 1204+33	SBC to reroute to Chicago Bureau of Electricity duct package attached to 95 th Street Bridge. Adjustment completed by September 1, 2005.
Com Ed/ IDOT	Power Feed For Tunnel Lighting conflicts with retaining wall. Potential conflict with ramp grading.	Near 97 th St. Station 144+60 SB I-57	The ITS/Lighting contractor will construct a temporary electric service during contract 62583. Contractor to contact Ms. LaShawn Greer (773) 838-4194 to coordinate the installation. Adjustment completed by September 1, 2005.

Revised 06-10-2005

COM ED	Duct to transformer in potential conflict with knee wall.	95 th Street Station 1205+25	Com Ed will verify depth of conduit. If a conflict exists, a sleeve will be required through the wall. Adjustment to be made during the roadway contract.
CTA - DC POWER FEED TO TRACKS	(6H, 4W) duct in potential conflict with retaining wall and mainline grading.	79 th St Station 1314+16	Duct to be protected by concrete slab or land bridge by roadway contractor.

 05/27/05

The above represents the best information available to the Department and is included for the convenience of the bidder. The applicable portions of Articles 105.07 and 107.31 of the Standard Specifications shall apply.

RESTRICTION ON GUARANTEED WORKING DAYS

Effective: January 21, 2003

All temporary lane closures during the period governed by guaranteed working days will not be permitted during the hours of 6:00 a.m. to 9:00 a.m. and 3:00 p.m. to 6:00 p.m. Monday through Friday.

All lane closure signs shall not be erected any earlier than one-half (1/2) hour before the starting hours listed above. Also, these signs should be taken down within one-half (1/2) hour after the closure is removed.

Failure to Open Traffic Lanes to Traffic: Should the Contractor fail to completely open and keep open all the traffic lanes to traffic in accordance with the limitations specified above, the Contractor shall be liable and shall pay to the Department the amount of \$250 per lane blocked, not as a penalty but as liquidated and ascertained damages, for each and every 15 minute interval or a portion thereof that a lane is blocked outside the allowable time limitations. The Department may deduct such damages from any monies due the Contractor. These damages shall apply during the period governed by guaranteed working days and any extensions of that contract time.

COORDINATION WITH ADJACENT AND/OR OVERLAPPING CONTRACTS

This contract abuts and /or overlaps with other concurrent Contracts as listed below. Each Contract includes work items requiring close coordination between the Contractors regarding the sequence and timing for the execution of such work items.

67TH ST. SB & NB C-D SYSTEM & RAMPS Contract 62590 (Dan Ryan Contract 7)

<u>Location</u>	<u>Starting Date</u>	<u>Tentative Completion Date</u>
67 th to 71 st ST	Under Construction	June - 2005
		Revised 06-10-2005

USE OF MULTIPLE PLANTS IN THE SAME CONSTRUCTION ITEM

The Contractor has the option to simultaneously use central-mixed, or shrink-mixed concrete from more than one plant, in the same construction item. However, the following criteria shall be met:

- a) For each plant the cement, fly ash, ground granulated blast-furnace slag, microsilica, and high-reactivity metakaolin shall be the same materials and from the same source. This requirement may not be changed by Articles 1001.04, 1010.03, 1014.02, 1015.02, and 1016.02.
- b) For each plant the fine aggregate shall be the same type and gradation.
- c) For each plant the coarse aggregate shall be the same material and from the same source. This requirement may not be changed by Article 1004.02 (e).
- d) For each plant the admixtures shall be the same material and from the same source.
- e) For each plant the mix design material proportions and water/cement ratio shall be the same. The required cement factor for central-mixed concrete shall be increased to match truck-mixed or shrink-mixed concrete, if the latter two types of mixed concrete are used.
- f) The maximum slump difference between deliveries of concrete shall be 19mm (0.75 in.) when tested at the jobsite. If the difference is exceeded, but test results are within specification limits, the concrete may be used. The Contractor shall take immediate corrective action and test subsequent deliveries of concrete until the tolerance has been met, for each day, the first three truck loads of delivered concrete from each plant shall be tested for slump. Thereafter, when a specified test frequency for slump is to be performed, it shall be conducted for each plant at the same time.
- g) The maximum air content difference between deliveries of concrete shall be 0.9 percent when tested at the jobsite. If the difference is exceeded, but test results are within specification limits, the concrete may be used. The contractor shall take immediate corrective action and test subsequent deliveries of concrete, until the tolerance has been met for each day, the first three truck loads of delivered concrete from each plant shall be tested for air content. Thereafter, when a specified test frequency for air content is to be performed, it shall be conducted for each plant at the same time.
- h) Compressive strength tests shall be performed and taken at the jobsite for each plant. When a specified compressive strength is to be performed, it shall be conducted for each plant at the same time. The difference between plants for their compressive strength mean shall not exceed 2070 kPA (300 psi). The compressive strength standard deviation for each plant shall not exceed 3450 kPA (500 psi). The mean and standard deviation requirements shall apply to any point of time for testing. Corrective action will be required if the tolerance is exceeded.
- i) The Maximum haul time difference between deliveries of concrete shall be 15 minutes. If the difference is exceeded, but haul time is within specification limits, the concrete may be used. The contractor shall take immediate corrective action and check subsequent deliveries of concrete. Until the tolerance has been met.

If the Contractor does not consistently meet all criteria for providing uniform concrete during construction, the Engineer shall not allow delivery from multiple plants or require the Contractor to take additional corrective action. If the Engineer allows additional corrective action and it is unsuccessful, delivery from multiple plants will not be allowed.

Added 06-10-2005

ILLINOIS ON-THE-JOB TRAINING

Supplement to State Required Contract Provisions Federal-Aid Construction Contracts

In addition to the Contractor's equal employment opportunity affirmative action efforts undertaken as required by FHWA-1273 that is part of this contract, including the Training Special Provision where applicable, the Contractor shall conform to the provisions of this Special Provision.

The purpose of Part II of FHWA-1273 and the Training Special Provision is to develop the skills of individuals through participation in approved apprenticeship and other joint training programs that will enhance the ability of the trainees to become members of the unions and to become full journeymen in the type of trade or job classification involved. Training programs aimed toward qualifying more minority group members and women for union membership, and upgrading of minorities and women apprentices in the construction trades is the primary affirmative action objective of these provisions.

In a cooperative affirmative action effort, the Department has agreed with certain construction trades to undertake outreach efforts intended to improve and increase opportunities for the participation of minority and women in the performance of this contract. The Carpenters, Cement masons, and Laborers will undertake to assign apprentices from the local area of recruitment. It is the responsibility of the Contractor to work with these and all trades in order to realize the goal that affirmative action holds out for the local minority and female workforces.

In addition, the Department has contracted with local community based organizations to provide referrals of individuals interested in working in the construction trades. For this contract, United Services is designated as the responsible Supportive Service Consultant to provide the assistance and referral services related to the affirmative action efforts of this Special Provision. The Supportive Service Consultant will be responsible for providing assistance and referrals to the Contractor for the applicable classifications. Also, the Supportive Service Consultant will provide screening, tutoring, and pre-referral training to individuals interested in working in the applicable crafts. It is the responsibility of the Contractor to work with this consultant in order to realize the goal that affirmative action holds out for the local minority and female workforces.

This Special Provision is an affirmative action effort and is not intended, and shall not be used, to discriminate against any applicant for employment or on-the-job training based on minority group or gender status. Furthermore, this Special Provision is in addition to all other EEO/Affirmative Action obligations of this contract.

The Contractor will be reimbursed at a rate of \$5.00 per hour plus fringe benefits for training the employees referred by the Supportive Service Consultant to work on this contract in accordance with this Special Provision. The number of trainees per trade shall be as follows: Carpenters, 1 trainee(s); Cement Masons, 1 trainee(s); Laborers, 2 trainee(s). This reimbursement will be made even though the Contractor receives additional training program funds from other sources including the Training Special Provision, provided such other source does not specifically prohibit the Contractor from receiving other reimbursement. It is not required that all trainees be on board for the entire length of the contract.

The Contractor shall provide for the maintenance of records and furnish periodic reports documenting his/her performance under this Special Provision.

Added 06-10-2005

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
E20200G1	V-PARTHEN QUINQ 1G	EACH	1,304.000					
K0030400	PERENNIAL PLANT DAYLI	UNIT	13.000					
XX004046	AERIAL CABLE REMOVAL	FOOT	370.000					
XX005128	STRIP SEAL EXP JT ASY	FOOT	167.000					
XX005489	STEEL CASING 48	FOOT	129.000					
XX104800	COMB CC&G TBV.12	FOOT	6,343.000					
X0300057	MAN TA 6D T1FCL R-PLT	EACH	3.000					
X0301295	ELECT MAN REMOVAL	EACH	8.000					
X0301898	E MAN 3'X4'X4' W24F&L	EACH	8.000					
* X0320001	PVC CON T 2 (S40)	FOOT	219.000					
X0320080	ROD & CL DUCT EX COND	FOOT	610.000					
X0320815	SLEEPER SLAB	FOOT	206.000					
X0320868	BRACED EXCAVATION SPL	CU YD	216.000					
X0321072	BRIDGE FENCE RAIL	FOOT	694.000					
X0321519	CONDUIT SUPPORT SYS	L SUM	1.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322122	METALLIZE STRUCT STL	L SUM	1.000				
X0322256	TEMP INFO SIGNING	SQ FT	144.000				
X0322425	C BRK 1P 70/480 EXCT	EACH	2.000				
* X0322671	STAB CONSTR ENTRANCE	SQ YD	1,857.000				
X0322679	C FDN TY P BM TS CONT	EACH	2.000				
X0322706	ELCBL C 12 10C	FOOT	512.000				
X0322741	LPS34.5MH12MA3G 1.50A	EACH	1.000				
X0322859	WEED CONTR PRE-EM GRN	POUND	20.000				
X0323426	SED CONT DR ST INL CL	EACH	30.000				
X0323574	MAINTAIN LIGHTING SYS	CAL MO	18.000				
X0323710	REMOV COND ATT TO STR	FOOT	760.000				
X0323830	DRAINAGE SCUPPR DS-11	EACH	10.000				
X0323907	COMMUNICATIONS VAULT	EACH	6.000				
X0324112	BARRIER BASE	FOOT	1,039.000				
X0324198	REMOV ASB CEM CONDUIT	FOOT	795.000				
* X0324210	C EN RC 4-4 CNC 2X2	FOOT	160.000				
* REVISED : JUNE 9, 2005							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
X0324212	C EN RC 6-4 CNC 2X3	FOOT	40.000					
* DELETED								
* DELETED								
X0324225	CONTR TRAF 16LB P CAB	EACH	2.000					
X0324414	CON EN RC 1-3 CNC	FOOT	48.000					
X0324420	PVC CON T 4 (S40)	FOOT	68.000					
X0324433	LT TOWER SERV PAD 6	SQ FT	411.000					
X0324455	DRILL/SET SOLD P SOIL	CU FT	185,131.000					
X0324456	DRILL/SET SOLD P ROCK	CU FT	152.000					
X0324478	PVC CON T 3 (S40)	FOOT	150.000					
X0324486	C F 24D 1.25AR 15BC 9	FOOT	54.000					
X0324487	C F 30D 1.5AR 16.5BC	FOOT	11.000					
X0324491	CONC MED WALL 18 WIDE	FOOT	435.000					
X0324493	CONC MEDIAN SURF SP	SQ FT	527.000					
X0324571	MAINT ST LTG SYS CHGO	L SUM	1.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0324697	SOIL STABILIZERS	POUND	528,845.000				
X0324698	APPLY DUST SUP AGENTS	UNIT	196.000				
X0324706	CF 30D 1.25AR17.25B 9	FOOT	18.000				
X0324864	DRAIN CONNECTIONS	FOOT	212.000				
X0324872	CIP T/D WSS RAMP DISB	SQ FT	156.000				
X0325015	ADJ FR & LID	EACH	6.000				
X0325016	CLEAN EX MH & HH	FOOT	4.000				
X0325017	COMBINED SEWER T2 8"	FOOT	56.000				
X0325018	C ENC RC 3-2 CNC 2X2	FOOT	20.000				
* DELETED							
* DELETED							
X0325021	INTER 7 WIRE LOCAL	EACH	1.000				
X0325022	INTER 7 WIRE MASTER	EACH	1.000				
X0325023	LPS32.5MH12MA7G11.5IO	EACH	6.000				
X0325024	LPS34.5MH12MA3G 15 BC	EACH	3.000				
			* REVISED : JUNE 9, 2005				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0325025	LPS34.5MH12MA3G 17.25	EACH	2.000				
X0325026	LPS34.5MH12MA7G 15 BC	EACH	3.000				
X0325027	MED & PVT REM (SPL)	SQ YD	560.000				
X0325028	P CITY STL 7 32.5 IO	EACH	6.000				
X0325029	PVC CON IN DCT 2-3"	FOOT	194.000				
X0325030	TR & BKFIL 2-4 DUCTS	FOOT	448.000				
* DELETED							
* X0325050	C ENC RC 4-4 2-2 2X3	FOOT	394.000				
* X0325051	C ENC RC 6-4 2-3 2X4	FOOT	31.000				
* X0325052	C ENC RC 5-4 1-2 2X3	FOOT	34.000				
* X0325053	C ENC RC 6-4 2-2 2X4	FOOT	35.000				
* X0325054	C ENC RC 5-4 3-2 2X4	FOOT	431.000				
X0329888	REM EX ST LIGHT EQUIP	L SUM	1.000				
X0656300	PAVEMENT REM & REPL	SQ YD	74.000				
X0712400	TEMP PAVEMENT	SQ YD	11,045.000				
X0933900	PVC CON T 3 (S80)	FOOT	295.000				
X0934000	PVC CON T 4 (S80)	FOOT	405.000				
X0934800	MA STL MONOTUBE 20	EACH	1.000				
X0934900	MA STL MONOTUBE 26	EACH	2.000				
X0935000	MA STL MONOTUBE 30	EACH	2.000				
							* REVISED : JUNE 9, 2005

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
X6063600	COMB CC&G TM4.24	FOOT	5,086.000					
X6065740	CONC MED SURF 5 MOD	SQ FT	14,493.000					
X6370920	CONC BAR 1F 42HT	FOOT	478.000					
X6370930	CONC BAR 2F 32HT	FOOT	420.000					
X6640210	TEMP CH LK FENCE PORT	FOOT	14,693.000					
X6643300	CH LK FENCE REMOV CTA	FOOT	270.000					
X6643310	CH LK FN REM/RE-E CTA	FOOT	100.000					
X6700410	ENGR FLD OFF A SPL	CAL MO	15.000					
X7011015	TR C-PROT EXPRESSWAYS	L SUM	1.000					
X7013820	TR CONT SURVEIL EXPWY	CAL DA	330.000					
X7015000	CHANGEABLE MESSAGE SN	CAL MO	144.000					
* X7040600	FUR TEMP CONC BARRIER	FOOT	510.000					
X8100060	CON T 4 GALVS PVC CTD	FOOT	48.000					
X8110125	CON ATS 4 GALVS PVC	FOOT	1,100.000					
* X8150200	TR & BKFIL W SCRN	FOOT	882.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0018800	DRAINAGE SYSTEM	L SUM	1.000				
Z0018940	DRILL EX MAN/HANDHOLE	EACH	13.000				
Z0030020	IMP ATTEN FRD NAR TL2	EACH	2.000				
Z0030070	IMP ATTEN SU NAR TL3	EACH	2.000				
Z0030240	IMP ATTN TEMP NRD TL2	EACH	4.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	14.000				
Z0030340	IMP ATTN REL NRD TL2	EACH	4.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	5.000				
Z0047300	PROTECTIVE SHIELD	SQ YD	4,727.000				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0056220	SAND MOD IMP ATT REM	EACH	1.000				
Z0068400	STEEL CASINGS 42	FOOT	159.000				
Z0075300	TIE BARS	EACH	91.000				
Z0076600	TRAINEES	hour	3,000.000		0.800		2,400.000
* Z0076705	OJT (LABORER TR)	hour	2,000.000		14.970		29,940.000
* Z0076710	OJT (CARPENTER TR)	hour	1,000.000		15.930		15,930.000
* Z0076715	OJT (CEMENT MASON TR)	hour	1,000.000		19.990		19,990.000
20100110	TREE REMOV 6-15	UNIT	3,369.000				
			* REVISED : JUNE 9, 2005				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
44000500	COMB CURB GUTTER REM	FOOT	23,935.000					
44000600	SIDEWALK REM	SQ FT	8,580.000					
44000700	APPROACH SLAB REM	SQ YD	450.000					
44001980	CONC BARRIER REMOV	FOOT	938.000					
44003100	MEDIAN REMOVAL	SQ FT	241.000					
* 44004250	PAVED SHLD REMOVAL	SQ YD	7,276.000					
44004260	PAVED SHLD REMOVAL SP	SQ YD	250.000					
44004400	PAVT REMOVAL SPL	SQ YD	542.000					
44201351	CL C PATCH T1 10 1/2	SQ YD	150.000					
44201355	CL C PATCH T2 10 1/2	SQ YD	290.000					
44201360	CL C PATCH T4 10 1/2	SQ YD	412.000					
48202400	BIT SHLD SUPER 6	SQ YD	560.000					
48300600	PCC SHOULDERS 11	SQ YD	752.100					
48300700	PCC SHOULDERS 12	SQ YD	126.200					
50100300	REM EXIST STRUCT N1	EACH	1.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50100400	REM EXIST STRUCT N2	EACH	1.000				
50100500	REM EXIST STRUCT N3	EACH	1.000				
50102400	CONC REM	CU YD	1.000				
50104650	SLOPE WALL REMOV	SQ YD	43.000				
50200100	STRUCTURE EXCAVATION	CU YD	13,811.000				
50200410	ROCK EXC STRUCT SPL	CU YD	27.000				
50300225	CONC STRUCT	CU YD	5,452.000				
50300255	CONC SUP-STR	CU YD	784.000				
50300260	BR DECK GROOVING	SQ YD	1,943.000				
50300300	PROTECTIVE COAT	SQ YD	13,196.000				
50300310	ELAST BEARING ASSY T1	EACH	24.000				
50300510	RUSTICATION FINISH	SQ FT	34,916.000				
* 50500105	F & E STRUCT STEEL	L SUM	1.000				
* 50500405	F & E STRUCT STEEL	POUND	2,770.000				
50500505	STUD SHEAR CONNECTORS	EACH	15,144.000				
50700209	UNTREATED TIMBER LAG	SQ FT	40,859.000				
			* REVISED : JUNE 9, 2005				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
50700211	FUR SOLDIER PILES HP	FOOT	3,698.000					
50700213	FUR SOLDIER PILES BU	FOOT	79.000					
50700215	FUR SOLDIER PILES WS	FOOT	31,247.000					
50800205	REINF BARS, EPOXY CTD	POUND	852,040.000					
50900905	REM & RE EX RAILING	FOOT	11.000					
51100100	SLOPE WALL 4	SQ YD	11.000					
51205200	TEMP SHT PILING	SQ FT	5,040.000					
51500100	NAME PLATES	EACH	1.000					
5421D012	P CUL CL D 1 12 TEMP	FOOT	85.000					
550A0340	STORM SEW CL A 2 12	FOOT	5,368.000					
550A0360	STORM SEW CL A 2 15	FOOT	270.000					
* 550A0380	STORM SEW CL A 2 18	FOOT	1,405.000					
550A0400	STORM SEW CL A 2 21	FOOT	34.000					
550A0410	STORM SEW CL A 2 24	FOOT	1,184.000					
550A0420	STORM SEW CL A 2 27	FOOT	1,370.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
60618324	CONC MEDIAN SURF 6 SP	SQ FT	7,366.000					
60618390	CONC MED SURF CORR	SQ FT	444.000					
63000000	SPBGR TY A	FOOT	138.000					
63100045	TRAF BAR TERM T2	EACH	3.000					
63100085	TRAF BAR TERM T6	EACH	4.000					
63100167	TR BAR TRM T1 SPL TAN	EACH	5.000					
* 63200310	GUARDRAIL REMOV	FOOT	600.000					
63700805	CONC BAR TRANS	FOOT	142.000					
66400305	CH LK FENCE 6	FOOT	2,992.000					
66410300	CH LK FENCE REMOV	FOOT	9,270.000					
* 66900200	NON SPL WASTE DISPOSL	CU YD	19,481.000					
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000					
66900530	SOIL DISPOSAL ANALY	EACH	6.000					
67100100	MOBILIZATION	L SUM	1.000					
70101800	TRAF CONT & PROT SPL	L SUM	1.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
78100100	RAISED REFL PAVT MKR	EACH	32.000					
78100300	REPLACEMENT REFLECTOR	EACH	762.000					
78200100	MONODIR PRIS BAR REFL	EACH	758.000					
78200410	GUARDRAIL MKR TYPE A	EACH	32.000					
78200530	BAR WALL MKR TYPE C	EACH	20.000					
78201000	TERMINAL MARKER - DA	EACH	5.000					
78300100	PAVT MARKING REMOVAL	SQ FT	12,061.000					
80700140	GROUND ROD 5/8 X 10	EACH	68.000					
80800525	TEMP WP60 CL4 15MA	EACH	6.000					
* 81000600	CON T 2 GALVS	FOOT	2,405.000					
81000800	CON T 3 GALVS	FOOT	227.000					
81012805	CON T 3 PVC ENC CONC	FOOT	1,016.000					
81023750	CON ENC C 3 PVC	FOOT	343.000					
81200100	CON EMB STR 1 GALVS	FOOT	15.000					
81200120	CON EMB STR 2 GALVS	FOOT	15.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK - -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price	
* 81200230	CON EMB STR 2 PVC	FOOT	384.000					
81301010	JUN BX SS ES 10X8X4	EACH	2.000					
81400200	HD HANDHOLE	EACH	24.000					
81400205	HD HANDHOLE SPL	EACH	2.000					
81500200	TR & BKFIL F ELECT WK	FOOT	4,192.000					
81800700	A CBL 3-1C2 AL MESS W	FOOT	890.000					
82102310	LUM SV HOR MT 310W	EACH	6.000					
83600300	LIGHT POLE FDN 30D	FOOT	60.000					
83700250	LT TOWER FDN 44D	FOOT	180.000					
84200700	LIGHTING FDN REMOV	EACH	9.000					
84200705	LIGHTING FDN REM PART	EACH	36.000					
85000200	MAIN EX TR SIG INSTAL	EACH	7.000					
87301155	ELCBL C SIGNAL 12 7C	FOOT	662.000					
87301185	ELCBL C SIGNAL 12 19C	FOOT	792.000					
87301805	ELCBL C SERV 6 2C	FOOT	426.000					
			* REVISED : JUNE 9, 2005					

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62695

State Job # - C-91-074-04
 PPS NBR - 1-74823-0615
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - (1516.1,1717&1818)R-9

Project Number
 IM-NHI094-3/393/060

Route
 FAI 94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87800100	CONC FDN TY A	FOOT	12.000				
87900200	DRILL EX HANDHOLE	EACH	1.000				
89000100	TEMP TR SIG INSTALL	EACH	2.000				
* 89502300	REM ELCBL FR CON	FOOT	1,624.000				
89502375	REMOV EX TS EQUIP	EACH	2.000				
89502385	REMOV EX CONC FDN	EACH	19.000				
* REVISED : JUNE 9, 2005							