	LOCA	LOCATION				
ROAD	ALIGNMENT	STATION	OFFSET	6-15 (UNIT)		
76TH	76TH ST.	70+96.9	39.2 RT	12		
			TOTAL	12		

### TREE REMOVAL (OVER 15 UNITS)

	LOCA	TION		TREE REMOV
ROAD	ALIGNMENT	STATION	OFFSET	(UNIT)
LAFAYETTE	LAFAYETTE	104+10	33.2 LT	34
			TOTAL	34

### CHAIN LINK FENCE REMOVAL

ŁOCATION	AL TONIMENT	FROM		то		CH LK FENCE
	ALIGNMENT	STATION	OFFSET	STATION	OFFSET	REMOV (FOOT)
76th STREET	76TH ST.	71+65.7	49.6 LT	72+53.1	48.7 LT	87
76th STREET	76TH ST.	71+59.4	33.0 RT	72+47.5	32.4 RT	88
76th STREET	76TH ST.	74+49.4	48.4 LT	75+29,1	50.0 LT	80
76th STREET	76TH ST.	74+45.8	32.6 RT	75+28.2	33.0 RT	82
					TOTAL	337

# COMBINATION CURB AND GUTTER REMOVAL

RAMP/WALL	AL TOUR (FAIT	FR	ОМ	то		COMB CURB
	ALIGNMENT	STATION	OFFSET	STATION	OFFSET	GUTTER REM (FOOT)
76th STREET	76TH ST.	69+70	LT	71+19	LT	160
LAFAYETTE AVE.	LAFAYETTE	103+92	LT	104+90	LT	98
76th STREET	76TH ST.	69+70	RT	71+13.4	RT	162
LAFAYETTE AVE.	LAFAYETTE	101+70	LT	102+79.5	LT	110
LAFAYETTE AVE.	LAFAYETTE	101+70	RT	102+91	RT	121
76th STREET	76TH ST.	71+53	RT	72+20	RT	75
76th STREET	76TH ST.	71+58.4	LT	72+20	LT	73
LAFAYETTE AVE.	LAFAYETTE	103+89.4	RT	104+90	RT	101
76th STREET	76TH ST.	74+77.2	LT	75+44.4	LT	74
STATE ST.	STATE	137+92	LT	138+10	LT	18
76th STREET	76TH ST.	74+77.2	RT	75+35.8	RT .	63
STATE ST.	STATE	136+56	LT	137+05	LT	49
STATE ST.	STATE	136+56	RT	137+05	RT	51
76th STREET	76TH ST.	76+10	RT	76+36	· RT	30
76th STREET	76TH ST.	76+07.5	LT	76+36	LT	39
STATE ST.	STATE	137+97	RT	138+10	RT	13
					TOTAL	1237

### BITUMINOUS SURFACE REMOVAL - BUTT JOINT

LOCATION	FROM		т	BIT SURF	
	ALIGNMENT	STATION	ALIGNMENT	STATION	REM BUTT JT (SQ YD)
76th STREET	76TH ST.	69+70	76TH ST.	69+74.5	22
LAFAYETTE AVE.	LAFAYETTE	101+70	LAFAYETTE	101+74.5	18
LAFAYETTE AVE.	LAFAYETTE	104+85.5	LAFAYETTE	104+90	18
76th STREET	76TH ST.	76+31.5	76TH ST.	76+36	22
STATE ST.	STATE	136+56	STATE	136+60.5	33
STATE ST.	STATE	138+05.5	STATE	138+10	32
				TOTAL	145

### APPROACH SLAB REMOVAL

LOCATION	FROM		T	APPROACH	
	ALIGNMENT	STATION	ALIGNMENT	STATION	SLAB REM (SQ YD)
76th STREET	76TH ST.	72+19.7	76TH ST.	72+49.7	228
76th STREET	76TH ST.	74+47.2	76TH ST.	74+77.2	222
	-			TOTAL	450

### MEDIAN AND PAVEMENT REMOVAL (SPECIAL)

LOCATION	FROM		T	MED & PAV'T	
	ALIGNMENT	STATION	ALIGNMENT	STATION	REM (SPL) (SQ YD)
76th STREET	76TH ST.	68+86.9	76TH ST.	70+90	286
76th STREET	76TH ST.	76+10	76TH ST.	78+11.1	274
				TOTAL	560

#### SIDEWALK REMOVAL

SIDEWALK REMOVAL							
ROAD	ALIGNMENT	OFFSET	FROM STATION	TO STATION	SIDEWALK REMOVAL (SQ FT)		
76th ST.	76TH ST.	LT	70+00	71+15	816		
76th ST.	76TH ST.	RT	70+50	71+10	661		
LAFAYETTE	LAFAYETTE	LT	102+22.6	102+27.2	69		
LAFAYETTE	LAFAYETTE	LT	103+93.8	104+07.5	128		
76th ST.	76TH ST.	LT	71+60	72+52.6	616		
76th ST.	76TH ST.	RT	71+53	72+48	616		
76th ST.	76TH ST.	LT	74+49	75+43	651		
76th ST.	76TH ST.	RT	74+46	75+36	594		
76th ST.	76TH ST.	RT	76+10	76+23	91		
				TOTAL	4242		

# BITUMINOUS SURFACE REMOVAL 2"

STA.

\* (1516.1, 1717 & 1818) R-9

TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

LOCATION	FROM		T	BIT SURF	
	ALIGNMENT	STATION	ALIGNMENT	STATION	REM VAR DP (SQ YD)
76th STREET	76TH ST.	69+74.5	76TH ST.	71+72.5	1141
LAFAYETTE AVE.	LAFAYETTE	101+74.5	LAFAYETTE	102+06.2	548
LAFAYETTE AVE.	LAFAYETTE	102+69.2	LAFAYETTE	104+85.5	487
76th STREET	76TH ST.	75+21.1	76TH ST.	76+31.5	727
STATE ST.	STATE	136+60.5	STATE	137+16.3	415
STATE ST.	STATE	137+78.6	STATE	138+05.5	198
				TOTAL	3516

### MEDIAN REMOVAL

LOCATION	FROM		T	MEDIAN	
	ALIGNMENT	STATION	ALIGNMENT	STATION	REM (SQ FT)
76th STREET	76TH ST.	71.80.8	76TH ST.	72+19.7	100
76th STREET	76TH ST.	74+77.2	76TH ST.	75+19.6	141
				TOTAL	241

### PAVEMENT REMOVAL

LOCATION	FROM		T	PAVEMENT	
	ALIGNMENT	STATION	ALIGNMENT	STATION	(SQ YD)
76th STREET	76TH ST.	71+72.5	76TH ST.	72+19.7	322
76th STREET	76TH ST.	74+77.2	76TH ST.	75+21.1	301
				TOTAL	623

ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 94 (DAN RYAN EXPRESSWAY) SCHEDULE OF QUANTITIES 76TH STREET BRIDGE - SHEET 1 SCALE: NONE DRAWN BY: RTM 05/06/05 DATE: MARCH 25, 2005 CHECKED BY: JPA

KNIGHT