TEMPORARY SEQUENCE OF OPERATION

MOVEMENT N		6 1			4 —8 4 —▶						F
PHASE	2+6 4+8						А				
INTERVAL	1	2	3A	3B	4	5	6A	6B	60	6D	S
CHANGE TO			4-	⊦8			2+6			Н	
US RTE. 12/45 (MANNHEIM RD.) N/B ALL SIGNALS	G	G	Y	R	R	R	R	R	R	R	R
US RTE. 12/45 (MANNHĒIM RD.) S/B ALL SIGNALS	G	G	Ϋ́Υ	R	R	R	R	R	R	R	R
PROSPECT AVE. (EAST OF TRACKS) W/B ALL SIGNALS	R	R	R	R	G	G	Y	R	R	R	R
PROSPECT AVE. (WEST OF TRACKS) W/B NEAR SIDE SIGNALS	R	R	R	R	G	G	G	G	Y	R	R
PROSPECT AVE. (WEST OF TRACKS) W/B FAR SIDE SIGNALS	R	R	R	R	G	G	G	G	Y	R	R
PROSPECT AVE. E/B ALL SIGNALS	R	R	R	R	G	G	G	G	Y	R	R
PEDESTRIAN SIGNALS CROSSING PROSPECT AVE. ON WEST SIDE OF US RTE. 12/45	*W	**FL DW	D₩	DW	DW	DW	DW	DW	DW	DW	D A
PEDESTRIAN SIGNALS CROSSING US RTE. 12/45 ON SOUTH SIDE OF PROSPECT AVE.	DW	D.W	D₩	DW	*W	**FL DW	DW	DW	DW	DW	R K

F.A.P. RTE.	SECTION	COUNTY	TOTAL	SHEE NO.
330	0 2004-018TS COOK		28	19
STA.		TO STA.		
FED. ROA	D DIST. NO. 1 ILLIN	OIS FED. AID	PROJEC1	-

CONTRACT NO. 62737

- * TO APPEAR ONLY UPON PUSHBUTTON ACTUATION
- •• FLASHING 'S TO TERMINATE AT THE COMPLETION OF THE PEDESTRIAN INTERVAL CLEARANCE.

TEMPORARY RAILROAD PREEMPTION SEQUENCE OF OPERATION

					PREEMPTOR NUMBER 2					
CHANGE FROM NORMAL SEQUENCE OF OPERATION INTERVAL NUMBER	1		4							
RAILROAD PREEMPTION SEQUENCE OF OPERATION INTERVAL NUMBER		1B	1C	1D	2	3	4	5	CLEAR TO	
CHANGE TO RAILROAD PREEMPTION SEQUENCE OF OPERATION INTERVAL NUMBER	1B	2	1D	2	3	4	SECUENC		SEQUENCE	
US RTE. 12/45 (MANNHEIM RD.) N/B ALL SIGNALS	Y	R	R	R	R	R	R	G	Δ	
US RTE. 12/45 (MANNHEIM RD.) S/B ALL SIGNALS	Υ	R	R	R	R	R	R	G	Δ	
PROSPECT AVE. (EAST OF TRACKS) W/B ALL SIGNALS	R	R	Y	R	R	R	R	R	Δ	
PROSPECT AVE. (WEST OF TRACKS) W/B NEAR SIDE SIGNALS	R	R	G	G	G →G	Υ	R	R	Δ	
PROSPECT AVE. (WEST OF TRACKS) W/B FAR SIDE SIGNALS	R	R	G	G	G → G	Υ	R	R	Δ	
PROSPECT AVE. E/B ALL SIGNALS	R	R	Y	R	R	R	R	R	Δ	
PEDESTRIAN SIGNALS CROSSING PROSPECT AVE. ON WEST SIDE OF US RTE, 12/45	FL DW	DW	DW	DW	DW	DW	DW	DW	Δ	
PEDESTRIAN SIGNALS CROSSING US RTE. 12/45 ON SOUTH SIDE OF PROSPECT AVE.		DW	FL DW	DW	DW	DW	DW	D₩	Δ	
INTERNALLY ILLUMINATED NO RIGHT TURN SIGNS	NRT	NRT	NRT	NRT	NRT	NRT	NRT	NRT	Δ	
INTERNALLY ILLUMINATED NO LEFT TURN SIGNS	NLT	NLT	NLT	NLT	NLT	NLT	NLT	NLT	Δ	
NDT - WAS BLOUT TURNY OR	<u></u>							HOLD		

☐ = RAILROAD PREEMPTION SEQUENCE SHALL PROVIDE THE PROPER CLEARANCE INTERVAL TO RESUME THE NORMAL SEQUENCE OF OPERATION OR PROPER CLEARANCE INTERVAL TO DISPLAY AN EMERGENCY VEHICLE INTERVAL (IF APPLICABLE) AFTER RAILROAD PREEMPTION INTERVAL 5 IS TERMINATED.

W = ILLUMINATED PERSON = WALK

FL = ILLUMINATED FLASHING HAND = FLASHING DON'T WALK

DW = ILLUMINATED SOLID HAND = DON'T WALK

TS-19

DATE ILLINOIS DEPARTMENT OF TRANSPORTATION TEMPORARY SEQUENCE OF OPERATION AND RAILROAD PREEMPTION SEQUENCE OF OPERATION, US RTE. 12/45 (MANNHEIM RD.) AND PROSPECT AVE. SCALE: NONE

KAM ENGINEERING, INC. CONSULTING ENGINEERS 707A Davis Road, Suite 205 Eigin, Winois 60123-1369

DRAWN BY: RV/MD DESIGNED BY: DS CHECKED BY: AS/KG DATE: FEBRUARY, 2005

...\Mannneis\Presp Emr ARSeq.sht 02/16/2005 10:35:31 AM

NRT = "NO RIGHT TURN" OR

NLT = "NO LEFT TURN" OR