| FA.P. | SECTION | COUNTY | TOTAL SHEET | NO. 2 | STA. | TO STA. | FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

CONTRACT NUMBER: 62739

	PERCENTAGES		URBAN 80'l. FEO. 20'l. STATE			
				CONSTRUCTION TYPE CODE		
	SUMMARY OF QUANTITIES		TOTAL	Y031-1F	Y031-1F	Y031-1F
CODE#	I TEM	UNIT	TOTAL QUANTITIES	IL. RTE. 21 AT OAKTON STREET	IL. RTE. 21 AT MAIN STREET	INTERCONNECT IL. RTE. 21 (MILWAUKEE AVE.) FROM OAKTON STREET TO MAIN STREET
67100100	MOBILIZATION	L SUM	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.33	0.33	0.34
70100 3 <u>1</u> 10	TRAFFIC CONTROL AND PROTECTION, STANDARD 701921	L SUM	1	0.33	0.33	0.34
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.33	0.33	0.34
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1363			1363
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1680			1680
81400100	HANDHOLE	EACH	5			5
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 10	FOOT	3254			3254
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	781		781	
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3260			3260
87900200	DRILL EXISTING HANDHOLE	EACH	4		,	4
88500100	INDUCTIVE LOOP DETECTOR .	EACH	10		10	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	1	-1	-
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET(SPECIAL)	EACH	. 1		1	
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1	
X8050015	SERVICE INSTALLATION, POLE MOUNT	EACH	1		1	,
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1	
XX002856	RE-OPTIMIZATION OF TRAFFIC SIGNAL SYSTEMS	L. SUM	1 .			
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	35		35	
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	35		35	

GENERAL NOTES:

- 1. ALL CONSTRUCTION SHALL BE PERFORMED ACCORDING TO THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AS PROMULGATED BY ILLINOIS DEPARTMENT OF TRANSPORTATION, DISTRICT 1 TRAFFIC SIGNAL SPECIFICATIONS AND THE PROJECT SPECIAL PROVISIONS.
- 2. THE EXACT LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE THE INSTALLATION OF THE TRAFFIC SIGNAL SYSTEM. FOR LOCATION OF UTILITIES CALL J.U.L.I.E. TOLL-FREE: 1-800-892-0123.

REVISION		ILLINOIS DEPARTMEN	T OF TRANSPORTATION			
NAME	DATE	SUMMARY OF				
	+	GENERAL NOTES- ILL. RTE. 21 (MILWAUKEE AVE.)				
			MILWAUKEE AVE.)			
		OAKTON STREET				
		COULTA N. T. C	DO AWAL DV			

SCALE: N.T.S. DATE 09-20-04

DESIGNED BY N.B. CHECKED BY D.B./M.S.

INFRASTRUCTURE ENGINEERING, INC. 29 S. LASALLE ST. SUJITE 345 CHICAGO. IL. 60603-1557 PHONE 312.425.9560 FAX 312.425.9564