

F.A.U. RTE. 1581	SECTION *	COUNTY	TOTAL SHEETS 29	SHEET NO. 3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (0202 & 0208) RS-8
62748

SUMMARY OF QUANTITIES					URBAN 100% STATE	
CODE NO.	ITEM DESCRIPTION	UNIT	1000-2A	CONSTRUCTION TYPE CODE		
			TOTAL QUANTITY	1000-2A		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31	31		
40600300	AGGREGATE (PRIME COAT)	TON	152	152		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	513	513		
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	210	210		
42001300	PROTECTIVE COAT	SQ YD	167	167		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	500	500		
44000600	SIDEWALK REMOVAL	SQ FT	500	500		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500		
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	7946	7946		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	731	731		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	107	107		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	162	162		
60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2		
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3		
60300310	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	10	10		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6216	6216		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2017.6	2017.6		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	74196	74196		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5776	5776		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	3000	3000		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2766	2766		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	692	692		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1008.8	1008.8		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37098	37098		

• SPECIALTY ITEM

SUMMARY OF QUANTITIES					URBAN 100% STATE	
CODE NO.	ITEM DESCRIPTION	UNIT	1000-2A	CONSTRUCTION TYPE CODE		
			TOTAL QUANTITY	1000-2A		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2938	2938		
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1500	1500		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1383	1383		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	346	346		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1109	1109		
88600600	DETECTOR LOOP REPLACEMENT	FOOT	1392	1392		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154.2	154.2		
X0322749	BITUMINOUS REMOVAL OVER PATCHES	SQ YD	1248	1248		
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	6372	6372		
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	3295	3295		
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	68087	68087		
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1317	1317		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	150	150		

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAU ROUTE 1581 (111TH STREET)
US 45 (96TH AVE) TO IL 7 (SOUTHWEST HWY)

SUMMARY OF QUANTITIES

SCALE: VERT. DRAWN BY
HORIZ. CHECKED BY
DATE

4/1/2005 11:24:54 AM K:\1102306\10000\10000\Sums_01urp.dgn