F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-0561	COOK	47	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62795

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY 1000 URBAN 90% FED 10% STATE
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,091	1,091
25200110	SODDING, SALT TOLERANT	SQ YD	1,091	1,091
30103000	SHAPING AND GRADING ROADWAY	UNIT	83	83
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	516	516
42001300	PROTECTIVE COAT	SQ YD	5,938	5,938
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	399	399
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	48,563	48,563
44201771	CLASS D PATCHES, TYPE IV, 10"	SQ YD	30	30
* 56109210	WATER VALVES TO BE ADJUSTED	EACH	10	10
* 56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	53	53
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	113	113
60600605	CONCRETE CURB, TYPE B	FOOT	237	237
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	234	234
67100100	MOBILIZATION	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	26	26
X0324872	CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES	SQ FT	324	324
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
~~Z0078600~~	~~TRAINEES~~	~~HOUR~~		
XX001109	PORTLAND CEMENT CONCRETE ALLEY PAVEMENT, 8"	SQ YD	117	117
XX152400	SAND CUSHION, 3-INCH	CU YD	450	450

~~Θ Y080~~
* SPECIALTY ITEMS

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5202, PHONE: (312) 938-0300

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59th ST TO 47th ST (WELLS ST SIDEWALKS)

SUMMARY OF QUANTITIES

SCALE: NONE | DRAWN BY: LC
DATE: MARCH 4, 2005 | CHECKED BY: JAL

03/02/2005 03:34:52 PM

M:\P4C46B\CIVIL\4-CNTR\Add_Cntr\SUM\SHG\General\SC59HUDP.dgn