

SIDEWALK ITEMS

STATION TO STATION	SHEET	SAND CUSHION, 3-INCH	TOPSOIL FURNISH AND PLACE, 4"	SODDING, SALT TOLERANT	PROTECTIVE COAT	PCC SIDEWALK 5 INCH	CLASS D PATCHES, TYPE IV, 10"	STEEL PLATE BEAM GUARDRAIL, TYPE A	CAST IN PLACE TACTILE/ DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES
		CU YD	SO YD	SO YD	SO YD	SO FT	SO YD	FOOT	SO FT
WELLS STREET									
535+32.53 TO 536+75.00	1	9	24	24	104	933			
536+75.00 TO 541+50.00	2	24	70	70	328	2,626			33
541+50.00 TO 546+00.00	3	26	72	72	336	2,858		40	
546+00.00 TO 551+00.00	4	42	87	87	498	4,484		131	16
551+00.00 TO 556+00.00	5	18	77	77	251	1,916			
556+00.00 TO 559+00.00	6	10	34	34	159	1,060			
559+00.00 TO 561+75.00	7	24	0	0	461	2,629	30		64
561+75.00 TO 566+75.00	8	21	55	55	316	2,270			
566+75.00 TO 571+75.00	9	25	83	83	301	2,709			
571+75.00 TO 576+75.00	10	24	79	79	288	2,596			16
576+75.00 TO 581+75.00	11	24	74	74	292	2,561			16
581+75.00 TO 586+50.00	12	21	27	27	277	2,240		63	18
586+50.00 TO 591+25.00	13	28	77	77	339	3,050			16
591+25.00 TO 596+25.00	14	26	79	79	313	2,815			18
596+25.00 TO 601+25.00	15	33	44	44	416	3,533			25
601+25.00 TO 606+25.00	16	29	77	77	375	3,175			44
606+25.00 TO 611+25.00	17	42	83	83	500	4,502			
611+25.00 TO 614+99.43	18	24	49	49	384	2,606			58
TOTALS		450	1091	1091	5,938	48,563	30	234	324

ALLEY AND DRIVEWAY SCHEDULE

	PCC ALLEY PAVEMENT, 8"	PCC DRIVEWAY PAVEMENT, 8 INCH	CONCRETE CURB, TYPE B	SUB-BASE GRANULAR MATERIAL, TYPE B 4"
	SO YD	SO YD	FOOT	SO YD
WELLS STREET				
538+62.88	33		32	33
545+47.40		18		18
551+54.00		11		11
552+13.73		9		9
552+49.06		9		9
553+13.56		9		9
556+26.13		6		6
558+08.24		9		9
558+37.30		21	48	21
559+08.52		18		18
561+29.60		45		45
561+80.91		24		24
562+57.53		24		24
563+34.21		16		16
578+64.07		7		7
583+45.85	15		18	15
584+45.95		11		11
601+10.75	21		22	21
605+21.94	20		23	20
612+87.23	15		22	15
613+42.29		53		53
614+48.77		24		24
SUB-TOTALS	104	314	165	418
55TH STREET				
20+28.05		20		20
21+01.33		21		21
21+33.33	13		13	13
21+68.33		25	32	25
22+26.01		19	27	19
SUB-TOTAL	13	85	72	98
TOTALS	117	399	237	516

F.A.I. RITE. SECTION COUNTY TOTAL SHEETS SHEET NO. 90/94 2004-0561 COOK 47 9
 STA. TO STA. TO STA. TO STA.
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT 62795



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 59th ST TO 47th ST (WELLS ST SIDEWALKS)
SCHEDULE OF QUANTITIES
 SCALE: NONE DRAWN BY: LC
 DATE: MARCH 4, 2005 CHECKED BY: JAL

02/24/2005 05:25:06 PM