

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 2.3 SQ. M. (25.70 SQ. FT.)

	NS ARE IN MILLIMETERS (INCHES) ESS OTHERWISE SHOWN.
REVISIONS DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION
R. MIRS 9-15-97 R. MIRS 12-11-97 T. RAMMACHER 2-2-99	TEMPORARY INFORMATION SIGNING
	SCALE: DRAWN BY: BUR. OF DESIGN
	DATE 10/18/2002 CHECKED BY
	TC22

REVISION DATE: 02/02/99