

URBAN
1000

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-------------|-------------|--------|--------------|-----------|
| 2503 | 2004-116 RS | KANE | 20 | 4 |

CONTRACT CONTRACT 62858

| Pay Item | Description | Unit | Total |
|------------|--|--------|---------|
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 2.00 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 9.00 |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 1.00 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1.00 |
| 40600980 | BITUMINOUS SURFACE REMOVAL - BUTT JOINT | SQ YD | 118.00 |
| 40601000 | BITUMINOUS REPLACEMENT OVER PATCHES | TON | 97.00 |
| 42001300 | PROTECTIVE COAT | SQ YD | 36.00 |
| 44000006 | BITUMINOUS SURFACE REMOVAL 1 1/2" | SQ YD | 4527.00 |
| 44000116 | BITUMINOUS REMOVAL OVER PATCHES 4" | SQ YD | 140.00 |
| 44000132 | BITUMINOUS REMOVAL OVER PATCHES 8" | SQ YD | 140.00 |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 200.00 |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SQ YD | 158.00 |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SQ YD | 23.00 |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SQ YD | 45.00 |
| 60250200 | CATCH BASINS TO BE ADJUSTED | EACH | 4.00 |
| 60255500 | MANHOLES TO BE ADJUSTED | EACH | 4.00 |
| 60260100 | INLETS TO BE ADJUSTED | EACH | 4.00 |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 2.00 |
| 67100100 | MOBILIZATION | L SUM | 1.00 |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1.00 |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1.00 |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1.00 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 430.00 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 145.00 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 182.00 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 1668.00 |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 1020.00 |
| * 78000500 | THERMOPLASTIC PAVEMENT MARKING - LINE 8" | FOOT | 250.00 |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 900.00 |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 152.00 |
| * 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 55.00 |
| * 88600600 | DETECTOR LOOP REPLACEMENT | FOOT | 950.00 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 96.00 |
| X4066426 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70 | TON | 381.00 |
| 44300200 | STRIP REFLECTIVE CRACK CONTROL TREATMENT | FOOT | 2850.00 |
| 60266600 | VALVE BOXES TO BE ADJUSTED | EACH | 3.00 |

* SPECIALTY ITEMS

Rev. 4-13-05

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES