

CONTRACT NO. 62859				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	G-R-1-4	WILL	10	2
STA.			TO STA.	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

INDEX OF SHEETS

SHEET NO	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS, GENERAL NOTES & SUMMARY OF QUANTITIES
3-9	BRIDGE PLANS
10	DETOUR

STATE STANDARDS

STANDARD NO	DESCRIPTION
701301-02	LANE CLOSURE, 2L 2W, SHORT TIME OPERATIONS
702001-05	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE & GAS FACILITIES. (48 HOURS NOTIFICATION IS REQUIRED.)

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS & CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION & ORDERING OF MATERIAL.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINING WORK.

THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.

ALL DIMENSIONS SHALL BE FIELD VERIFIED PRIOR TO THE FABRICATION OF ANY STEEL.

WORK ON THE STRUCTURE SHALL BE DONE IN SUCH A MANNER THAT CLOSURE OF THE BRIDGE TO RIVER TRAFFIC (PERIODS WHERE THE BRIDGE IS RESTRICTED TO THE DOWN POSITION) IS KEPT TO A MINIMUM (4 HOURS MAXIMUM) AND COORDINATED WITH THE COAST GUARD.

RIVER TRAFFIC IS TO RE MAINTAINED AT ALL TIMES.

WORK THAT REQUIRES THE BRIDGE TO BE IMMOBILIZED SHALL BE DONE WITH THE BRIDGE REQUIREMENTS SHOWN ON THE DRAWINGS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE NOTIFICATION OF ALL EMERGENCY SERVICES, SCHOOL DISTRICTS, I.D.O.T.'S COMMUNICATION CENTER, SPRINGFIELD TRUCK PERMIT SECTION AND OTHER AGENCIES AFFECTED BY THE CLOSURE. THE CONTRACTOR SHALL ALSO BE RESPONSIBLE FOR POSTING SIGNS THAT WILL INDICATE THE DATES THE CLOSURE WILL BE IN PLACE.

THE CONTRACTOR SHALL CONTACT THE BUREAU OF TRAFFIC, SIGNALS UNIT AT (847) 705-4139 A MINIMUM OF 48 HOURS PRIOR TO CLOSURE SO THE DETOUR ROUTE TRAFFIC SIGNALS MAY BE ADJUSTED AS NECESSARY.

THE COST OF THE WORK INVOLVED IN "CLEANING AND PAINTING ADJACENT AREAS OF EXISTING STEEL STRUCTURES" AND "CLEANING AND PAINTING NEW METAL STRUCTURES" SHALL BE CONSIDERED INCLUDED IN THE COST OF "MECHANICAL WORK - LUMP SUM".

URBAN

LOCATION OF WORK: US 30 (WB)/CASS STREET OVER DES PLAINES RIVER				
				CONSTRUCTION TYPE CODE
SUMMARY OF QUANTITIES				SFTY - 2A
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	SN: 099-0101
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURES	SQ FT	48	48
X0323343	MECHANICAL WORK	L SUM	1	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
INDEX OF SHEETS
STATE STANDARDS
GENERAL NOTES
SUMMARY OF QUANTITIES

SCALE: VERT. _____
 DATE: _____ HORIZ. _____

DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 3/31/2005
 FILE NAME = c:\pcc\jw\m18388\m18388.dwg
 PLOT SCALE = 0.0000 / IN.
 USER NAME = jw