# GENERAL NOTES:

- 1. UTILITY LOCATIONS SHOWN ON THESE PLANS MAY NOT BE CORRECT OR COMPLETE. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE RESPECTIVE UTILITIES OF THE CITY OF CHICAGO. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL THE CHICAGO UTILITY ALERT NETWORK AT (312) 7447-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, CABLE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED). CONTACT THE CHICAGO DEPARTMENT OF WATER MANAGEMENT PERMIT SECTION AT (312) 747-7893 FOR WATER AND SEWER LOCATIONS.
- 2. THE CONTRACTOR SHALL NOT SET UP A YARD OR FIELD OFFICE ON IDOT PROPERTY WITHOUT WRITTEN PERMISSION FROM IDOT.
- 3. THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ABUTTING PROPERTY, UTILITIES, PEDESTRIANS, AND VEHICULAR TRAFFIC.
- 4. NIGHT OPERATIONS: WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTION IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AS WELL AS THE ADJOINING RESIDENTIAL AREAS.
- 5. SEE SPECIAL PROVISIONS FOR INTERIM COMPLETION DATES. SEWER TELEVISING IS REQUIRED BEFORE CONSTRUCTION BEGINS IN CONTRACT 62694. THE SECOND TELEVISING IS REQUIRED WHEN CONTRACT 62695 COMPLETES WORK IN A GIVEN STAGE. THIS CONTRACT HAS THE SAME COMPLETION DATE AS CONTRACT 62694.
- 6. HEAVY CLEANING OF EXISTING COMBINED SEWERS SHALL BE PAID FOR AS "CLEANING EXISTING SANITARY SEWERS".
- 7. THE CONTRACTOR SHALL CONTACT MWRD AT 312-751-5600 FOR NECESSARY WORK REQUIREMENTS AND PERMITS BEFORE ANY WORK CAN BEGIN ON 72ND STREET CROSSING.

### GENERAL NOTES: CITY OF CHICAGO

- 1. A PERMIT FROM THE DEPARTMENT OF WATER MANAGEMENT IS REQUIRED FOR ALL UNDERGROUND WORK INCLUDING TELEVISION SURVEYS, CLEANING, LINING, AND INSPECTIONS. THE DEPARTMENT OF WATER MANAGEMENT'S PERMIT MUST BE OBTAINED BY A LICENSED SEWER DRAIN LAYER PRIOR TO START OF CONSTRUCTION. THE LICENSED SEWER CONTRACTOR/ SUBCONTRACTOR MUST SUBMIT TWO SETS OF PLANS APPROVED BY THE DEPARTMENT OF WATER MANAGEMENT FOR THE ISSUANCE OF THE SEWER PERMIT TO BUREAU OF ENGINEERING SERVICES-SEWER SECTION, JARDINE PURIFICATION PLANT, EL+51, ROOM 313, 1000 E. OHIO ST., CHICAGO, IL 60611. INSPECTION WILL BE PROVIDED BY THE DEPARTMENT OF WATER MANAGEMENT.
- 2. IN CASE OF DAMAGE TO CITY OF CHICAGO SEWERS, PRIVATE AND PUBLIC DRAINS, SEWER STRUCTURES AND/OR BENCH MONUMENTS, THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE DEPARTMENT OF WATER MANAGEMENT AT (312) 744-0409 OR (312) 744-0408.
- 3. IN LOCATIONS WHERE THE MAIN SEWERS, DRAINAGE STRUCTURES, PUBLIC, AND PRIVATE DRAIN CONNECTIONS ARE DISTURBED OR DAMAGED DURING TELEVISING BY THE CONTRACTOR, IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO RESTORE AND REPLACE THE DAMAGED FACILITIES AT HIS/HER OWN EXPENSE TO THE SATISFACTION OF THE DEPARTMENT OF WATER MANAGEMENT. THE SEWER FLOWS MUST BE MAINTAINED AT ALL TIMES.
- 4. THE SEWER UNIT OF THE DEPARTMENT OF WATER MANAGEMENT MUST BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE OF CONSTRUCTION, WITH THE NAME AND TELEPHONE NUMBER OF THE RESIDENT ENGINEER WHO COULD BE CONTACTED FOR ANY SEWER EMERGENCY.
- 5. LOCAL ACCESS TO ALL SECONDARY STREETS MUST BE MAINTAINED. ADEQUATE PROVISION FOR PEDESTRIAN TRAFFIC MUST BE ASSURED AT ALL TIMES.
- 6. CITY OF CHICAGO WATER VALVE VAULTS AND SEWER STRUCTURES SHALL NOT BE CLOSED, COVERED OR OTHERWISE OBSTRUCTED DURING CONSTRUCTION WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT OF WATER MANAGEMENT.

#### SEWER TELEVISING AND CLEANING SCHEDULE

LETTER	RAMP/STREET	BEGIN STRUCTURE NUMBER	END STRUCTURE NUMBER	TOTAL LENGTH TO BE TELEVISED (FT)	TOTAL LENGTH TO BE CLEANED (FT)
Α	HALSTED STREET CROSSING	A1	A2	644	322
В	HALSTED STREET EXIT RAMP	B1	B5	660	330
С	W. 98TH PLACE	C1	C9	833	417
D	WENTWORTH AVE. CROSSING	D1	D2	690	173
Е	WENTWORTH AVE. EXIT RAMP	E1	E4	374	187
F	S. LAFAYETTE AVENUE	F1	F3	670	335
G	95TH EXIT RAMP	G1	G18	2390	1195
Н	89TH STREET CROSSING	H1	H4	355	89
I	87TH ENTRANCE & EXIT RAMPS	I1	I17	2885	1443
J	86TH STREET CROSSING	J1	J4	767	384
К	84TH STREET CROSSING	K1	K4	900	225
L	79TH-76TH C-D RAMP	L1	L3	1477	739
М	77TH STREET CROSSING	M1	M2	839	210
N	79TH-76TH C-D RAMP	N1	N8	926	463
0	74TH STREET CROSSING	01	02	400	100
Р	75TH-71ST C-D RAMP	P1	P6	356	178
Q	75TH-71ST C-D RAMP	Q1	Q3	426	213
*TAPED ONCE AFTER CONSTRUCTION				3184	
TAPED TWICE -BEFORE AND AFTER CONSTRUCTION				24816	
TOTAL				28000	7003

#### SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	FUNDING: 100% STATE Y007
67100100	MOBILIZATION	L SUM	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1
X0322787	CLEANING EXISTING SANITARY SEWERS	FOOT	7003
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	50
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	12
XX004812	VIDEOTAPING OF SEWERS	FOOT	28000
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

# IDOT HIGHWAY STANDARDS

STANDARD 701601-04 DESCRIPTION URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN

701606-04 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN

701701-04 URBAN LANE CLOSURE, MULTILANE INTERSECTION

702001-05 TRAFFIC CONTROL DEVICES

### INDEX OF SHEETS

SHEET DESCRIPTION

GENERAL NOTES, SUMMARY OF QUANTITIES, SEWER TELEVISING SCHEDULE, INDEX OF STATE STANDARDS, INDEX OF SHEETS

3-6 CONTRACT 62695 (17B) CONSTRUCTION SCHEDULE

SEWER TELEVISING KEY PLAN

8-27 SEWER TELEVISING PLANS

28 IDOT DISTRICT 1 DETAIL TC-17 (TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES PARTIAL RAMP CLOSURES

29 IDOT DISTRICT 1 DETAIL TC-22 (TEMPORARY INFORMATION SIGNING)

REVISIONS ILLINOIS
NAME DATE
F.A.I. 9
GENERAL NO
SCHEDUL

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

TOTAL SHEET NO.

62935

COUNTY

STA, 2200+00.00 TO STA, 2362+00.00

• (1516.1, 1717 & 1818) T-1

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

COOK 29

94

GENERAL NOTES, SUMMARY OF QUANTITIES, SCHEDULE OF QUANTITIES, & INDEX OF STATE STANDARDS

SCALE: NONE DRAWN BY: AMB
DATE: APRIL 15, 2005 CHECKED BY: TGB