

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	33
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER) (CONT.)

LOCATION	UNIT	REMARKS
STA. 625+27.6	29' LT	
STA. 627+2.8	56.5' RT	
STA. 643+4.6	39.3' RT	
STA. 643+42	39.4' RT	
STA. 643+99	27.1' RT	
STA. 644+15.4	38.4' RT	
STA. 644+97.4	42.4' RT	
STA. 645+00	41.2' RT	
STA. 645+33.1	27.6' RT	
STA. 645+43.3	28' RT	
STA. 645+53.6	55.4' RT	
STA. 645+97	26.3' RT	
STA. 646+22.2	26.8' RT	
STA. 646+45.6	25.5' RT	
STA. 646+60.2	24.2' RT	
STA. 661+52.1	42.1' RT	
STA. 661+72.7	41.5' RT	
STA. 661+91.3	40.5' RT	
STA. 662+23.2	41.3' RT	
STA. 662+42.2	42' RT	
STA. 667+39.5	37.5' RT	
STA. 238+97.4	18.7' RT	
STA. 239+30.9	18.8' RT	
STA. 258+81.8	20.5' LT	
STA. 259+19.8	29.8' RT	
TOTAL =	1782.5	

20100500 TREE REMOVAL, ACRES

LOCATION	ACRE	REMARKS
STA. 428+39.85 to STA. 429+26.09	LT 0.011	
STA. 429+86.00 to STA. 431+54.19	RT 0.105	
STA. 438+14.69 to STA. 438+47.75	LT 0.011	
STA. 456+50.10 to STA. 458+18.48	LT 0.011	
STA. 458+49.94 to STA. 459+38.94	LT 0.058	
STA. 460+28.00 to STA. 461+06.60	LT 0.007	
STA. 498+27.07 to STA. 500+19.55	RT 0.094	
STA. 513+86.54 to STA. 515+12.34	LT 0.025	
STA. 515+41.87 to STA. 516+00.00	LT 0.003	
STA. 520+05.38 to STA. 521+13.93	LT 0.016	
STA. 521+49.67 to STA. 523+62.70	LT 0.125	
STA. 524+49.09 to STA. 525+34.26	RT 0.043	
STA. 528+11.97 to STA. 528+52.81	RT 0.019	
STA. 535+72.48 to STA. 539+25.96	RT 0.177	
STA. 560+23.72 to STA. 568+66.30	LT 0.666	
STA. 594+95.50 to STA. 605+32.88	RT 0.838	
STA. 605+52.90 to STA. 608+04.50	RT 0.225	
STA. 613+23.78 to STA. 619+41.29	RT 0.502	
STA. 619+11.30 to STA. 620+53.14	LT 0.060	
STA. 632+32.05 to STA. 635+83.94	RT 0.308	
STA. 679+76.90 to STA. 690+83.89	RT 0.012	
STA. 703+75.82 to STA. 711+10.21	RT 0.175	
STA. 706+82.81 to STA. 715+19.34	LT 0.628	
STA. 740+09.03 to STA. 740+80.28	LT 0.008	
STA. 746+73.37 to STA. 747+01.68	LT 0.001	
STA. 748+51.48 to STA. 748+78.54	LT 0.002	
STA. 749+83.00 to STA. 750+51.42	LT 0.020	
STA. 749+77.49 to STA. 756+00.00	RT 0.500	
STA. 756+39.50 to STA. 757+71.68	RT 0.008	
STA. 759+14.48 to STA. 760+58.65	RT 0.075	
STA. 771+20.54 to STA. 771+71.27	LT 0.010	
STA. 771+87.69 to STA. 772+07.67	LT 0.008	
STA. 773+48.77 to STA. 774+06.65	LT 0.016	
STA. 774+25.81 to STA. 774+74.48	LT 0.012	
STA. 784+45.96 to STA. 785+35.72	LT 0.036	
STA. 784+35.00 to STA. 785+39.64	RT 0.056	
TOTAL =	4.87	

20200100 EARTH EXCAVATION

LOCATION	CU YD	REMARKS
THROUGHOUT PROJECT	214656	
TOTAL =	214656	

20200410 EARTH EXCAVATION (SPECIAL)

LOCATION	CU YD	REMARKS
STA. 500+70.61	45.84' LT 23	10' Radius around 1st Order Monument
STA. 646+80.05	41.84' RT 3	10' Radius around 1st Order Monument
TOTAL =	26	

20201200 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL

LOCATION	CU YD	REMARKS
STA. 432+91	151.1	(12" Depth for entire length of culvert at a slope of 1:1.5)
STA. 438+13	137.3	(18" Depth for entire length of culvert at a slope of 1:1)
STA. 517+98	118.0	(24" Depth for entire length of culvert at a slope of 1:1.5)
STA. 522+33	85.4	(18" Depth for entire length of culvert at a slope of 1:1.5)
STA. 619+34	82.0	(18" Depth for entire length of culvert at a slope of 1:1.5)
STA. 644+58.5	53.4	(18" Depth for entire length of culvert at a slope of 1:1.5)
STA. 732+53	109.0	(15" Depth for entire length of culvert at a slope of 1:1.5)
TOTAL =	736.20	

20800150 TRENCH BACKFILL

LOCATION	CU YD	REMARKS
STORM SEWER QUANTITIES	1362.22	
WATER MAIN IMPROVEMENTS	1725.00	
STA. 432+91	LT 49.3	CULVERT
STA. 438+13	76.3	AR CULVERT
STA. 444+38.8	56.3	AR CULVERT
STA. 470+63.6	19.8	AR CULVERT
STA. 496+41	109.0	AR CULVERT
STA. 512+25	21.7	AR CULVERT
STA. 517+98	78.8	AR CULVERT
STA. 522+33	124.1	AR CULVERT
STA. 528+38.19	89.4	AR CULVERT
STA. 529+89.01	83.0	AR CULVERT
STA. 552+46.67	95.3	AR CULVERT
STA. 556+20.01	55.7	AR CULVERT
STA. 584+14.64	RT 26.8	CULVERT
STA. 619+34	200.6	AR CULVERT
STA. 626+15.30	36.4	AR CULVERT
STA. 644+58.5	30.9	AR CULVERT
STA. 651+37	30.9	AR CULVERT
STA. 664+12.23	24.4	AR CULVERT
STA. 671+36.73	30.0	AR CULVERT
STA. 700+65.73	36.3	AR CULVERT
STA. 732+51.96	51.5	AR CULVERT
STA. 748+80.27	20.3	AR CULVERT
STA. 757+33	21.7	AR CULVERT
STA. 765+67	36.9	AR CULVERT
TOTAL =	4492.63	

21301052 EXPLORATION TRENCH 52" DEPTH

LOCATION	FOOT	REMARKS
STA. 410+10 to STA. 411+10	100	EVELYN WILKEN RESIDENCE, COULD NOT FIND DRAIN TILE
STA. 732+07 to STA. 732+46	64	
TOTAL =	164.00	

PLOT DATE = Tue Feb 08 14:32:57 2005
 PLOT SCALE = 1/8" = 100'-0"
 REFERENCE = REF#