CONTRACT NO. 64178

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	49
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BITUMINOUS SCHEDULE

STATIONING	BITUMINOUS LENGTH FEET	BITUMINOUS WIDTH FEET	BASE MATERIAL CU. YD.	BITUMINOUS AREA SQ. FT.	BITUMINOUS AREA SQ. YD.	35100100 AGGREGATE BASE CSE. TYPE A TON	31100100 SUB-BASE GRAN. MTRL. TYPE A TON	40600200 BIT PRIME TON	40600300 AGG. PRIME TON	X4066614 BIT. CONC. BIND. CSE. IL 19.0 N50 TON	X4066765 LEVEL BIND. MACH. MET TON	48202310 BIT. SHLDR. SUPERPAVE MIX, 5 1/2" SQ YD	48202315 BIT. SHLDR. SUPERPAVE MIX, 5 3/4" SQ YD	X4066424 BIT. CONC. SURF. CSE. MIX "D", N50 TON	X4066414 BIT. CONC. SURF. CSE. MIX "C", N50 TON	X4073131 BIT. CONC. FULL DEPTH 12.5" SQ. YD.	X4080020 INCIDENTAL BIT SURF SUP. N50 TON	70300100 SHORT TERM PAVT. MARKING FOOT	THICKNESS BIND. CSE. INCH	THICKNESS SURFACE INCH	THICKNESS LEVEL BIND. INCH	THICKNESS BASE INCH
IL 72 - Main line																						
369+82.08 - 370+49.7	67.62	125.4 - 40	156.47	3753.62	417.07		320.76	0.30	0.63							417.07		20.29	10.5	2		12
370+49.70 - 379+00	850.3	40	1422.49	34014.2	3779.35		2916.10	2.70	5.67							3779.35		255.09	10.5	2		12
379+00 - 380+00	100	40	151.03	4000.00	444.44		309.60	0.32	0.67							444.44		30.00	10.5	2		12
380+00 - 382+00	200	40	352.72	8011.21	890.13		723.08	0.64	1.34							890.13		60.00	10.5	2		12
382+00 - 383+41.4	141.4	40 - 53	410.75	6579.31	731.03		842.04	0.52	1.10							731.03		42.42	10.5	2		18
383+41.4 - 385+47.9	211.4	53	671.85	10946.1	1216.24		1377.29	0.87	1.82							1216.24		63.42	10.5	2		18
385+47.9 - 386+12.61	47.2	53 - 40	128.64	2830.16	314.46		263.72	0.22	0.47							314.46		14.16	10.5	2		18
386+12.61 - 386+25	25.0	40	62.81	491.2	54.58		128.76	0.04	0.08							54.58		7.50	10.5	2		18
386+25 - 387+50	125.0	40	431.88	5000	555.56		885.36	0.29	0.83	124.69	31.11			46.67				37.50	10	1.5	1	18
387+50 - 388+56	106.0	40	173.53	4239.97	471.11		355.74	0.24	0.71	105.14	26.38			39.57				31.80	10	1.5	1	24
388+56 - 390+56	200.0	40 - 53	424.46	9305	1033.89		870.14	0.58	1.55	279.74	57.90			86.85				60.00	10	1.5	1	24
390+56 - 394+11.83	355.83	53 - 40	579.96	18240.9	2026.76		1188.92	1.20	3.04	600.30	113.50			170.25				106.75	10	1.5	1	18
394+11.83 - 395+00	88.17	40	125.66	3526.83	391.87		257.60	0.21	0.59	91.36	21.94			32.92				26.45	10	1.5	1	18
395+00 - 402+57.4	757.4	40 - 26.5	606.36	27678.6	3075.40		1243.04	1.76	4.61	594.54	172.22			258.33				227.22	10	1.5	1	12
402+57.4 - 440+00	3742.6	24		89822.4	9980.27			5.71	14.97		558.89			838.34				1122.78		1.5	1	
440+00 - 475+00	3500	24		84000	9333.33			5.34	14.00		522.67			784.00				1050.00		1.5	1	
475+00 - 501+00	2600	24		62400	6933.33			3.97	10.40		388.27			582.40				780.00		1.5	1	
501+00 - 530+00	2900	24		69600	7733.33			4.42	11.60		433.07			649.60				870.00		1.5	1	
530+00 - 555+00	2500	24		60000	6666.67			3.81	10.00		373.33			560.00				750.00		1.5	1	
555+00 - 585+35.81	3035.81	24		72859.4	8095.49			4.63	12.14		451.11			680.02				910.74		1.5	1	
586+39.1 - 615+00	2860.9	24		68661.6	7629.07			4.36	11.44		424.99			640.84				858.27		1.5	1	
615+00 - 635+00	2000	24		48000	5333.33			3.05	8.00		298.67			448.00				600.00		1.5	1	
635+00 - 660+00	2500	24		60000	6666.67			3.81	10.00		373.33			560.00				750.00		1.5	1	
660+00 - 686+59	2659	24		63816	7090.67			4.06	10.64		397.08			595.62				797.70		1.5	1	
686+59 - 687+00	41	25 - 26	9.11	1034.46	114.94		18.67	0.07	0.17	3.82	6.44			9.65				12.30	10	1.5	1	12
687+00 - 689+50	250	26 - 32	182.70	7262.56	806.95		374.54	0.32	1.21	83.47	45.19			67.78				75.00	10	1.5	1	24
689+50 - 692+50	300	24 - 38	282.56	10708	1189.78		579.25	0.51	1.78	232.19	66.63			99.94				90.00	10	1.5	1	18
692+50 - 693+58.8	108.8	38	157.77	4090.88	454.54		323.44	0.24	0.68	102.07	25.45			38.18				32.64	10	1.5	1	24
693+58.8 - 695+10	151.2	38 - 50	202.96	6124.23	680.47		416.07	0.36	1.02	162.41	38.11			57.16				45.36	10	1.5	1	18
695+10 - 698+95.8	385.8	50 - 31	678.93	17374.6	1930.51		1391.81	0.90	2.90	514.65	108.11			162.16				115.74	10	1.5	1	18
698+95.8 - 701+43	247.2	31 - 24	120.05	6849.47	761.05		246.09	0.31	1.14	65.23	42.62			63.93				74.16	10	1.5	1	18
701+43 - 712+50	1107	24		26536.2	2948.46			1.26	4.42		165.11			247.67				332.10		1.5	1	
712+50 - 758+87	4637	24		110748	12305.33			5.28	18.46		689.10			1033.65				1391.10		1.5	1	
758+73.4 - 761+00	226.6	25 - 48	69.07	6213.46	690.38		141.59	0.25	1.04	52.59	38.66			57.99				67.98	10	1.5	1	12
761+00 - 767+50	650	30 - 38	406.02	23105.6	2567.29		832.34	1.25	3.85	500.11	143.77			215.65				195.00	10	1.5	1	12
767+50 - 769+63	213	38 - 50	209.77	8895.24	988.36		430.02	0.51	1.48	222.76	55.35			83.02				63.90	10	1.5	1	18
769+63 - 772+00	237	50	347.54	11850	1316.67		712.46	1.13	1.98	322.89	73.73			110.60				71.10	10	1.5	1	18
772+00 - 775+25	325	50 - 38	313.32	14723.5	1635.94		642.31	1.40	2.45	435.38	91.61			137.42				97.50	10	1.5	1	12
775+25 - 775+50	25	38 - 37	14.68	941.13	104.57		30.10	0.05	0.16	21.64	5.86			8.78				7.50	10	1.5	1	12
775+50 - 778+00	250	37 - 31	208.82	8580.3	953.37		428.07	0.44	1.43	163.87	53.39			80.08				75.00	10	1.5	1	18
778+00 - 780+58.21	258.21	31 - 25	85.52	7175.19	797.24		175.32	0.30	1.20	71.37	44.65			66.97				77.46	10	1.5	1	12
780+58.21 - 785+32.8	474.59	24		11889.4	1321.04			0.38	1.98		73.98			110.97				142.38		1.5	1	
Ash Ave.																						
South																						
198+75 - 199+80	105	26 - 81	114.32	3086.6	342.96		234.35	0.15	0.51							342.96				3		12
North																						
200+20 - 201+17.41	97.41	66 - 28	105.21	2840.7	315.63	215.68		0.14	0.47						53.03					3		12
Chestnut Ave.																						
South																						
218+38 - 219+80	142	22 & VAR	232.83	5148.07	572.01		477.30	0.41	0.86							572.01			10.5	2		12
North																						
220+20 - 221+62	142	26 & VAR	222.39	4867.91	540.88		455.89	0.39	0.81							540.88			10.5	2		12
Oak Ave.																						
South																						
238+28 - 239+80	152	24 & VAR	197.63	4441.05	493.45	405.13		0.21	0.74						82.90					3		12
North																						
240+20 - 242+12	192	26 & VAR	256.09	5599.85	622.21		524.98	0.18	0.93							622.21			10.5	2		12
Plum Ave.																						
South																						
257+38 - 259+80	242	17 & VAR	228.18	5916.82	657.42	467.77		0.28	0.99						110.45					3		12
North																						
260+20 - 262+12	192	21 & VAR	201.84	5174.74	574.97	413.78		0.16	0.86						96.60					3		12
Locust Ave.																						
South																						
278+63 - 279+78.5	115.5	24 & VAR	133.46	3524.61	391.62	273.60		0.17	0.59						65.79					3		12
North																						
280+19 - 281+37	118	26 & VAR	141.80	3651.25	405.69	290.69		0.12	0.61						68.16					3		12

PLOT DATE = Fri Feb 25 11:58:16 2005
FILE NAME = c:\pwworking\dot\d0064737\ov-bit.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = REF