CONTRACT NO. 64178

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	56
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ENTRANCE SCHEDULE

LOCATION			40600200 BIT PRIMB COAT TONS	35101400 AGG BASE CSE TYPE B TONS	X4080020 2" INC BITUMIN SURF TONS	42300300 PCC DRIVEWAY PAVEMBNT 7" SQ YD	542D0220 PIPE CUL CL. D TYPE 1 15" FOOT	542D0223 PIPE CUL CL. D TYPE 1 18" FOOT	542D0229 PIPE CUL CL. D TYPE 1 24" FOOT	542D0235 PIPE CUL CL. D TYPE 1 30" FOOT	542D0241 PIPE CUL CL. D, TYPE 1 36" FOOT	542D5491 PIP CUL CL. D, TYPE 1 EQRS 36" FOOT	542D5503 PIPE CUL CL. D, TYPE1 EQRS 48" FOOT	54213450 END SECTIONS 15" EACH	54213453 END SECTIONS 18" EACH	54213459 END SECTIONS 24" EACH	54213465 END SECTIONS 30" EACH	54213471 END SECTIONS 36" EACH	54214311 END SECTION EQRS, 36" EACH	#2001304 METAL END SECT. SPECIAL EACH	40200800 AGG. SURF CRSE. TYPE B TON	44000200 DRIVEWAY PAVEMBNT REMOVAL SQ YD
IL 72																						
513+54.00	FE	RT		39.83					48.00							2.00						
516+31.00	PE	LT		4.47		32.2																
519+87.00	PE	LT		4.98		34.8																
520+35.00	PE	RT	0.14	16.37	11.10		58.00							2.00								
526+39.00	FE	LT		64.45			48.00							2.00								
527+28.00	FE	LT		61.48			38.00							2.00								
529+82.00	PE	RT	0.19	22.06	14.56																	
529+82.00	MB	LT	0.05		3.89																	
537+13.00	PE	LT		5.18		34.6																
538+26.00	PE	LT		14.64		48.6																
540+22.00	FE	RT		66.90			46.00							2.00								
552+90.00	FE	LT		77.82																		
553+07.80	RD	RT																				
579+72.87	RD	LT										85.00							2.00		28.00	
582+12.00	FE	LT		84.23							46.00							2.00				
584+26.00	FE	RT		60.59																		
589+00.00	FE	RT		81.21																		
589+36.00	FE	LT		101.41																		
592+83.00	PE	RT	0.14	9.90	10.99		46.00							2.00								
593+75.00	FE	RT		70.35			48.00							2.00								
605+49.00	PE	RT	0.16	17.51	12.38																	
606+09.87	RD	LT																				
613+19.00	FE	RT		64.13																		
613+31.00	FE	LT		90.28																		
625+63.00	PE	LT	0.17	13.85	13.13																	
625+79.77	RD	RT																				
645+22.00	PE	RT	0.12	13.36	9.60		56.00							2.00								
645+22.00	FE	LT	0.40	86.23	31.09																	
647+14.00	PE	RT	0.12	11.75	9.02																	
648+94.00	FE	RT		69.63																		
651+85.00	FE	LT		78.02																		
659+34.00	FE	RT		71.02																		
663+10.00	PE	RT	0.15		11.86			54.00							2.00							
663+12.60	MB	LT	0.03		2.68																	
672+00.00	PE	LT	0.20	29.67	15.35								18.00							2.00		
672+31.00	PE	RT	0.18	23.39	14.43																	
685+15.00	CE	RT	0.19		14.66					44.00							2.00					
695+09.55	RD	LT										105.00							2.00			
695+23.00	CE	RT	0.14	15.99	10.75							36.00							2.00			
702+97.00	PE	RT	0.12	11.77	9.36																	
717+74.00	PE	RT	0.27	44.42	20.82			52.00							2.00							
735+83.00	FE	LT		45.23																		
735+88.00	FE	RT		59.42																		
749+74.00	FE	RT		68.74					50.00							2.00						

PLOT DATE = Tue Feb 09 14:23:20 2005
FILE NAME = C:\projects\64178\64178ent01cov-dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = REF