CONTRACT NO. 64178

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	61
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CULVERT PATCHING SCHEDULE

STATION	REMARKS	PATCH LT LANE (feet)	PATCH RT LANE (feet)	44201403 LENGTH OF TYPE 2 LT LANE (yd³/64)	44201403 LENGTH OF TYPE 2 RT LANE (yd³/64)	44201407 TYPE 3 LT LANE (yd³/64)	44201407 TYPE 3 RT LANE (yd³/64)	44201409 TYPE 4 LT LANE (yd³/64)	44201409 TYPE 4 RT LANE (yd³/64)
438 + 13	CULVERT PATCH	34	34					45.3	45.3
444 + 39	CULVERT PATCH	40	40					53.3	53.3
470 + 64	CULVERT PATCH	12	12			16.0	16.0		
496 + 41	CULVERT PATCH	27	27					36.0	36.0
512 + 25	CULVERT PATCH	19	19					25.3	25.3
517 + 98	CULVERT PATCH	41	41					54.7	54.7
522 + 33	CULVERT PATCH	79	87					105.3	116.0
528 + 38	CULVERT PATCH	40	40					53.3	53.3
529 + 89	CULVERT PATCH	41	41					54.7	54.7
552 + 47	CULVERT PATCH	38	38					50.7	50.7
619 + 34	CULVERT PATCH	64	68					85.3	90.7
626 + 15	CULVERT PATCH	15	15			20.0	20.0		
644 + 59	CULVERT PATCH	57	57					76.0	76.0
651 + 37	CULVERT PATCH	30	30					40.0	40.0
664 + 12	CULVERT PATCH	14	14			18.7	18.7		
671 + 37	CULVERT PATCH	14	14			18.7	18.7		
700 + 66	CULVERT PATCH	20	20					26.7	26.7
732 + 52	CULVERT PATCH	33	33					44.0	44.0
748 + 80	CULVERT PATCH	11	11	14.7	14.7				
757 + 52	CULVERT PATCH	22	22					29.3	29.3
765 + 67	CULVERT PATCH	10	10	13.3	13.3				
			TOTALS =	28.0	28.0	73.3	73.3	780.0	796.0
				56.0		146.7		1576.0	

TEMPORARY PATCHING SCHEDULE

STATION	REMARKS	PATCH LT LANE (feet)	PATCH RT LANE (feet)	Area of Patch (SQ. YDS.)	X4080020 Incidental Bituminous Surfacing (TON)	Thickness of Temp. Patch (inches)
438 + 13	CULVERT PATCH	34	34	90.67	10.15	2
444 + 39	CULVERT PATCH	40	40	106.67	11.95	2
470 + 64	CULVERT PATCH	12	12	32.00	3.58	2
496 + 41	CULVERT PATCH	27	27	72.00	8.06	2
512 + 25	CULVERT PATCH	19	19	50.67	5.67	2
517 + 98	CULVERT PATCH	41	41	109.33	12.25	2
522 + 33	CULVERT PATCH	79	87	221.33	24.79	2
528 + 38	CULVERT PATCH	40	40	106.67	11.95	2
529 + 89	CULVERT PATCH	41	41	109.33	12.25	2
552 + 47	CULVERT PATCH	38	38	101.33	11.35	2
619 + 34	CULVERT PATCH	64	68	176.00	19.71	2
626 + 15	CULVERT PATCH	15	15	40.00	4.48	2
644 + 59	CULVERT PATCH	57	57	152.00	17.02	2
651 + 37	CULVERT PATCH	30	30	80.00	8.96	2
664 + 12	CULVERT PATCH	14	14	37.33	4.18	2
671 + 37	CULVERT PATCH	14	14	37.33	4.18	2
700 + 66	CULVERT PATCH	20	20	53.33	5.97	2
732 + 52	CULVERT PATCH	33	33	88.00	9.86	2
748 + 80	CULVERT PATCH	11	11	29.33	3.29	2
757 + 52	CULVERT PATCH	22	22	58.67	6.57	2
765 + 67	CULVERT PATCH	10	10	26.67	2.99	2
				TOTAL =	**199.21**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

CULVERT AND TEMPORARY PATCHING SCHEDULE

PLOT DATE = Tue Feb 08 14:03:33 2005
FILE NAME = D:\proj\s\X4080020\1\X4080497\cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = REF