

# EARTHWORK AND SEEDING SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
549	116RS-1	OGLE	593	66
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	20200100		20200200		EARTH EXC ADJ SHRINK 25% EARTH		EMBANK (FILL) CU YD	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)		25200100	25000310	25000910	25001830	25000400	25000500	25000600	25200200	28000250	21101615	21101645
	EARTH EXC (CUT) CU YD	ROCK EXC CU YD	EARTH EXC ADJ SHRINK 25% EARTH CU YD	EARTH WORK BALANCE WASTE (+) SHORTAGE (-) CU YD	SODDING SQ YD	SEEDING CLASS 4 ACRE		SEEDING CLASS 1 MODIFIED ACRE	SEEDING CLASS 6 MODIFIED ACRE	NITROGEN FERTILIZER NUTRIENTS POUND	PHOSPHOROUS FERTILIZER NUTRIENTS POUND	POTASSIUM FERTILIZER NUTRIENTS POUND	SUPPLEMENTAL WATERING UNIT	TEMPORARY EROSION CONTROL SEEDING POUNDS	TOPSOIL FURNISH & PLACE					
															TOPSOIL FURNISH & PLACE					
															4"	12"				
																		SQ YD	SQ YD	
369 + 82 - 375 + 00	2632	0	1974	2	1972	731								9.06	9.06	9.06	50.43	43.15	731	
375 + 00 - 381 + 00	5657	0	4242	19	4224	1643								20.36	20.36	20.36	113.35	96.97	1643	
381 + 00 - 387 + 00	2845	0	2134	837	1297	3905								48.41	48.41	48.41	269.43	230.50	3905	
387 + 00 - 403 + 00	6521	0	4891	812	4078	3492	0.38	0.26	0.32	129.69	129.69	129.69	240.93	146.70	146.70	146.70	465.71	480.41	8313	
403 + 00 - 419 + 00	5526	0	4145	161	3984		0.43	0.84	0.36	146.70	146.70	146.70		231.30	231.30	231.30	734.29	734.29	7904	
419 + 00 - 435 + 00	5247	0	3935	3139	796		1.07	0.00	1.50	231.30	231.30	231.30		190.80	190.80	190.80	605.71	605.71	12442	
435 + 00 - 451 + 00	5493	0	4120	1172	2948		0.52	0.49	1.11	190.80	190.80	190.80		171.90	171.90	171.90	545.71	545.71	10233	
451 + 00 - 467 + 00	7765	0	5824	219	5604		1.03	0.18	0.70	171.90	171.90	171.90		156.60	156.60	156.60	497.14	497.14	9231	
467 + 00 - 483 + 00	5245	0	3934	1147	2786		0.69	0.10	0.95	156.60	156.60	156.60		182.70	182.70	182.70	580.00	580.00	8384	
483 + 00 - 499 + 00	13150	0	9862	794	9068		1.10	0.20	0.91	198.90	198.90	198.90		214.20	214.20	214.20	680.00	680.00	10723	
499 + 00 - 515 + 00	10654	0	7991	204	7787		0.91	0.28	0.84	182.70	182.70	182.70		171.90	171.90	171.90	545.71	545.71	9805	
515 + 00 - 531 + 00	7798	0	5848	2458	3390		0.70	0.66	1.02	214.20	214.20	214.20		227.70	227.70	227.70	680.00	680.00	11514	
531 + 00 - 547 + 00	9811	0	7358	16	7342		0.99	0.19	0.73	171.90	171.90	171.90		167.40	167.40	167.40	531.43	531.43	9260	
547 + 00 - 563 + 00	17600	0	13200	636	12563		1.51	0.00	1.02	227.70	227.70	227.70		189.00	189.00	189.00	600.00	600.00	12212	
563 + 00 - 579 + 00	6557	0	4918	576	4342		0.97	0.00	0.89	167.40	167.40	167.40		249.30	249.30	249.30	791.43	791.43	9015	
579 + 00 - 595 + 00	7454	0	5590	2443	3147		0.88	0.16	1.06	189.00	189.00	189.00		231.30	231.30	231.30	734.29	734.29	10149	
595 + 00 - 611 + 00	18286	0	13714	1208	12506		1.53	0.00	1.24	249.30	249.30	249.30		202.50	202.50	202.50	642.86	642.86	13431	
611 + 00 - 627 + 00	11064	0	8298	2560	5738		1.03	0.33	1.21	231.30	231.30	231.30		153.00	153.00	153.00	485.71	485.71	12399	
627 + 00 - 643 + 00	11507	722	9352	877	8475		0.93	0.00	1.32	202.50	202.50	202.50		159.30	159.30	159.30	505.71	505.71	10927	1159
643 + 00 - 659 + 00	4230	0	3172	543	2629		0.69	0.25	0.76	153.00	153.00	153.00		152.10	152.10	152.10	482.86	482.86	8235	
659 + 00 - 675 + 00	5167	0	3875	355	3520		0.81	0.00	0.96	159.30	159.30	159.30		152.10	152.10	152.10	482.86	482.86	8578	
675 + 00 - 691 + 00	5590	0	4192	437	3755		0.88	0.00	0.81	152.10	152.10	152.10		154.80	154.80	154.80	491.43	491.43	8163	
691 + 00 - 707 + 00	3720	0	2790	1187	1603		0.67	0.09	0.96	154.80	154.80	154.80		170.10	170.10	170.10	540.00	540.00	8325	
707 + 00 - 723 + 00	3826	0	2870	840	2030		0.65	0.28	0.96	170.10	170.10	170.10		186.30	186.30	186.30	591.43	591.43	9168	
723 + 00 - 739 + 00	4288	0	3216	356	2860		0.71	0.00	1.36	186.30	186.30	186.30		187.20	187.20	187.20	594.29	594.29	10014	
739 + 00 - 755 + 00	5593	0	4194	1290	2905		1.40	0.00	0.68	187.20	187.20	187.20		138.60	138.60	138.60	440.00	440.00	10079	
755 + 00 - 771 + 00	7802	0	5852	298	5554		0.77	0.00	0.77	138.60	138.60	138.60		207.90	207.90	207.90	660.00	660.00	7450	
771 + 00 - 785 + 33	5422	0	4066	756	3311		0.92	0.00	1.39	207.90	207.90	207.90							11170	
<b>SIDERROADS</b>																				
<b>ASH AVE</b>																				
198 + 50 - 201 + 25	291	0	218	0	218	125	0.00	0.00	0.00	1.54	1.54	1.54	8.59	7.35	7.35	125				
<b>CHESTNUT AVE</b>																				
218 + 25 - 221 + 75	685	0	514	6	508	412	0.00	0.00	0.00	5.11	5.11	5.11	28.43	24.32	24.32	412				
<b>OAK AVE</b>																				
238 + 25 - 242 + 25	597	0	448	6	441	551	0.00	0.00	0.00	6.84	6.84	6.84	38.05	32.55	32.55	551				
<b>PLUM AVE</b>																				
257 + 25 - 262 + 25	790	0	592	28	564	760	0.00	0.00	0.00	9.42	9.42	9.42	52.43	44.85	44.85	760				
<b>LOCUST AVE</b>																				
278 + 50 - 281 + 50	278	0	209	12	197	557	0.00	0.00	0.00	6.90	6.90	6.90	38.43	32.88	32.88	557				
<b>STORM SEWER</b>																				
1 + 25 - 5 + 00	24	0	18	70	-52	685	0.00	0.00	0.00	8.49	8.49	8.49	47.23	40.41	40.41	685				
<b>COLUMBINE</b>																				
75 + 32 - 78 + 50	2643	0	1982	16	1966	0	0.19	0.00	0.18	33.30	33.30	33.30	105.71	105.71	105.71	1812				
<b>MILE RD</b>																				
85 + 50 - 89 + 50	887	0	665	1510	-844	0	0.09	0.00	0.40	44.10	44.10	44.10	140.00	140.00	140.00	2377				
<b>CHERRY</b>																				
90 + 35 - 92 + 00	185	0	138	5	134	0	0.08	0.00	0.08	14.40	14.40	14.40	45.71	45.71	45.71	760				
<b>MT. MORRIS RD</b>																				
127 + 00 - 129 + 43	1827	0	1371	0	1371	0	0.15	0.00	0.14	26.10	26.10	26.10	82.86	82.86	82.86	1368				
<b>TOTAL</b>	<b>214656</b>	<b>722</b>	<b>161714</b>	<b>26996</b>	<b>134718</b>	<b>12859</b>	<b>23</b>	<b>4</b>	<b>25</b>	<b>4805</b>	<b>4805</b>	<b>4805</b>	<b>887</b>	<b>15508</b>	<b>15508</b>	<b>15508</b>	<b>262806</b>	<b>262806</b>	<b>1159</b>	

PLOT DATE = Tue Feb 08 14:03:48 2005  
 FILE NAME = C:\pwork\2004\17\080417\080417.dgn  
 PLOT NO = 08 / IN  
 REFERENCE = REF#