

SUMMARY OF QUANTITIES

CONTRACT NO. 64A10

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & T S	HENRY	90	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	90% FED 10% STATE	90% FEDERAL 5% STATE 5% CITY SIGNALS Y031-1F
				ROADWAY 1000-1A	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ. YD.	102	102	
40600990	TEMPORARY RAMP	SQ. YD.	66	66	
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	242	242	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ. YD.	910	910	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ. FT.	573	573	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ. YD.	1643	1643	
44000100	PAVEMENT REMOVAL	SQ. YD.	1147	1147	
44000122	BITUMINOUS REMOVAL OVER PATCHES 5 1/2"	SQ. YD.	787	787	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ. YD.	1887	1887	
44000500	COMBINATION CURB & GUTTER REMOVAL	FOOT	509	509	
44004250	PAVED SHOULDER REMOVAL	SQ. YD.	330	330	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ. YD.	20	20	
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ. YD.	46	46	
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ. YD.	100	100	
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ. YD.	61	61	
44213200	SAW CUTS	FOOT	324	324	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3054	3054	
48202310	BITUMINOUS SHOULDERS SUPERPAVE 5 1/2"	SQ. YD.	596	596	
50200400	ROCK EXCAVATION FOR STRUCTURES	CU. YD.	69	69	
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	16	16	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	626	626	

PLOT DATE = Wed Feb 09 11:41:15 2005
 FILE NAME = C:\projects\20050208\48202310.dgn
 PLOT SCALE = 1/8" = 1'-0"
 REFERENCE = SHEET #

SUMMARY OF QUANTITIES