

SUMMARY OF QUANTITIES

CONTRACT NO. 64A10				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & TS	HENRY	90	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	ITEM	UNITS	URBAN TOTAL	90% FED 10% STATE	90% FEDERAL 5% STATE 5% CITY
				ROADWAY 1000-1A	SIGNALS Y031-1F
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	184	184	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	729	729	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	50	50	
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1	
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1	
60107600	PIPE UNDERDRAINS 4"	FOOT	108	108	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	5	5	
60242400	INLETS, SPECIAL	EACH	6	6	
60242801	INLETS, SPECIAL, NO. 5	EACH	11	11	
60242802	INLETS, SPECIAL, NO. 6	EACH	1	1	
60242803	INLETS, SPECIAL, NO. 7	EACH	1	1	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1	
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4	4	
60500040	REMOVING MANHOLES	EACH	4	4	
60500060	REMOVING INLETS	EACH	1	1	
60500065	REMOVING INLETS, SPECIAL	EACH	2	2	
60600095	CLASS SI CONCRETE (OUTLET)	CU. YD.	1.2	1.2	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2572	2572	
* 66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

PLOT DATE = Wed Feb 09 11:41:16 2005
 FILE NAME = C:\projects\640598A\640598A.dgn
 PLOT NO = 10 / 10
 REFERENCE = REF1