

SCHEDULE OF QUANTITIES

CONTRACT NO. 64A10

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & TS	HENRY	90	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

25	IL 84	117+24		Stopbar White
22	Sta.	117+53	TO 117+74	Stopbar White
17	Sta.	117+75	TO 117+92	Stopbar White
29	Sta.	118+28		Stopbar White
93	TOTAL			

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	REMARKS
	IL 84	
2	Sta. 109+60	Two-way amber
2	Sta. 110+00	Two-way amber
2	Sta. 110+40	Two-way amber
2	Sta. 110+80	Two-way amber
2	Sta. 111+20	One-way amber - painted island
2	Sta. 111+60	One-way amber - painted island
2	Sta. 112+00	One-way amber - painted island
2	Sta. 112+40	One-way amber - painted island
2	Sta. 112+80	One-way amber - painted island
2	Sta. 113+20	One-way amber - painted island
2	Sta. 113+60	One-way amber - painted island
2	Sta. 114+00	One-way amber - painted island
2	Sta. 114+40	One-way amber - painted island
2	Sta. 114+80	One-way amber - painted island
2	Sta. 115+20	One-way amber - painted island
2	Sta. 115+60	One-way amber - painted island
1	Sta. 116+00	One-way crystal - left turn lane
2	Sta. 116+00	Two-way amber
1	Sta. 116+40	One-way crystal - left turn lane
2	Sta. 116+40	Two-way amber
1	Sta. 116+80	One-way crystal - left turn lane
1	Sta. 116+80	Two-way amber
1	Sta. 117+20	One-way crystal - left turn lane
2	Sta. 117+20	Two-way amber
1	Sta. 118+30	One-way crystal - left turn lane
2	Sta. 118+30	Two-way amber
1	Sta. 118+70	One-way crystal - left turn lane
2	Sta. 118+70	Two-way amber
1	Sta. 119+10	One-way crystal - left turn lane
2	Sta. 119+10	Two-way amber
1	Sta. 119+50	One-way crystal - left turn lane
2	Sta. 119+50	Two-way amber
2	Sta. 119+90	One-way amber - painted island
2	Sta. 120+30	One-way amber - painted island
2	Sta. 120+70	One-way amber - painted island
2	Sta. 121+10	One-way amber - painted island
2	Sta. 121+50	One-way amber - painted island
2	Sta. 121+90	One-way amber - painted island
2	Sta. 122+30	One-way amber - painted island
2	Sta. 122+70	One-way amber - painted island
2	Sta. 123+10	One-way amber - painted island
2	Sta. 123+50	One-way amber - painted island
2	Sta. 123+90	One-way amber - painted island
1	Sta. 124+25	One-way crystal
2	Sta. 124+30	One-way amber - painted island
2	Sta. 124+70	Two-way amber
1	Sta. 125+05	One-way crystal
84	TOTAL	

Z0017100 DOWEL BARS

EACH	LOCATION	LANE WIDTH	LENGTH	REMARKS
	IL 84			
20	LT Sta. 116+75	13.0	6.7	1 LANE - Over Storm Sewer
24	LT Sta. 123+47	14.0	8.9	1/3 of road width - Over Storm Sewer
24	L & R Sta. 123+47	14.0	8.9	1/3 of road width - Over Storm Sewer
20	RT Sta. 116+75	13.0	6.7	1 LANE - Over Storm Sewer
24	RT Sta. 123+47	14.0	8.9	1/3 of road width - Over Storm Sewer
112	TOTAL			

Z0023600 FILLING EXISTING CULVERTS

EACH	LOCATION	REMARKS
	IL 84	
1	Sta. 121+65	18" CMP
1	TOTAL	

Z0075300 TIE BARS

EACH	LOCATION	SPACING	REMARKS
	IL 84		
40	RT Sta. 110+01	TO 111+00	PCC BASE COURSE
36	RT Sta. 124+39	TO 125+28	PCC BASE COURSE

REMARKS

76 TOTAL

X0323691 MONITORING WELL ABANDONMENT

EACH	LOCATION	OFFSET (ft)	REMARKS
1	IL 84 Sta. 118+21	33.8	
1	IL 84 Sta. 119+12	33.3	
1	5th Street (S of IL 84) Sta. 9+33	20.4	
3	TOTAL		

X4080020 INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50

TON	LOCATION	LANE WIDTH	LENGTH	REMARKS
	IL 84			
1.6	LT Sta. 116+75	13.0	6.7	1 LANE - 3" thick - temp patch over SS
2.3	LT Sta. 123+47	14.0	8.9	1/3 road - 3" thick - temp patch over SS
2.3	L & R Sta. 123+47	14.0	8.9	1/3 road - 3" thick - temp patch over SS
1.6	RT Sta. 116+75	13.0	6.7	1 LANE - 3" thick - temp patch over SS
2.3	RT Sta. 123+47	14.0	8.9	1/3 road - 3" thick - temp patch over SS
10.2	TOTAL			NOTE - ADDITIONAL INCIDENTAL BITUMINOUS SURFACING IS ON THE ENTRANCE SCHEDULE AND BITUMINOUS SCHEDULE

X5011100 FOUNDATION REMOVAL

EACH	LOCATION	OFFSET (ft)	REMARKS
	IL 84		
1	RT Sta. 116+86	49	
1	TOTAL		

PLOT DATE = Mon Apr 11 14:38:57 2005
 FILE NAME = C:\p2005\64A10\64A10.dgn
 PLOT SCALE = 50.0000 / IN.
 REFERENCE = #REF#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT. DATE
HORIZ. DATE
DRAWN BY
CHECKED BY

SCHEDULE OF QUANTITIES