

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & TS	HENRY	90	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BITUMINOUS SCHEDULE

STATIONING	35300500	X4066414		20201400				21001000	44000100	44000030		70300100		70301000
	PCC BASE CRS 10"	BIT CONC SURF CSE, SP MIX "C", N50		SUB-BASE GRANULAR MATERIAL, TYPE A				GEO TECH FAB FOR GR STAB	PAV REM	BIT SURF REMOVAL (VARIABLE DEPTH)		SHORT TERM PAV MARKING		WORK ZONE PAVT MARK REMOVAL
	SQ YD	THKNS	TON	12" SQ YD	15" SQ YD	24" SQ YD	TOTAL TONS	SQ YD	SQ YD	MAINLINE SQ YD	SHOULDER SQ YD	MEDIAN FOOT	INCL-TRN LN, SB & AR FOOT	SQ FT
IL 84 (LT LANE)														
109 + 29 - 110 + 1									0.8			0.0		0.0
110 + 1 - 116 + 46									27.0			0.0	597.0	66.3
116 + 46 - 118 + 47												0.0		0.0
118 + 47 - 121 + 28												0.0		0.0
121 + 28 - 121 + 78										76.7		0.0		0.0
121 + 78 - 123 + 52		2.5 - 2.0	15.6							366.0	123.9	0.0		0.0
123 + 52 - 124 + 94		2.5 - 2.0	16.4							416.7	129.8	0.0		0.0
124 + 94 - 125 + 28														
IL 84 (RT LANE)														
109 + 29 - 110 + 1	1.4			20.7			14.1	20.7				YELLOW	WHITE-TRN LN	2.7
110 + 1 - 111 + 0	29.3			63.2			43.2	63.2				36.0		4.0
111 + 0 - 111 + 52				44.6			30.5	44.6				24.0		2.7
111 + 52 - 113 + 50				225.6			154.2	225.6				60.0		6.7
113 + 50 - 114 + 44					160.2		136.8	160.2				36.0		4.0
114 + 44 - 120 + 50		2.5	23.6		1196.1		1021.7	1196.1				192.0	585.0	86.3
120 + 50 - 121 + 8		2.5	7.2			153.0	209.1	153.0				24.0		2.7
121 + 8 - 121 + 28		2.5	2.5			51.8	70.8	51.8				12.0		1.3
121 + 28 - 121 + 78		2.5	6.2			122.9	168.0	122.9				24.0		2.7
121 + 78 - 124 + 39		2.5	32.5			489.9	669.6	489.9		65.6		84.0		9.3
124 + 39 - 124 + 84	15.9	2.5	5.6			58.8	80.3	58.8		60.4		24.0		2.7
124 + 84 - 125 + 28	8.1	2.5	5.8			51.9	70.9	51.9		58.6		24.0		2.7
5TH STREET (N OF IL 84)														
ENTIRE SIDEROAD														
10 + 27 - 11 + 26					513.2		438.4	513.2	344.5			YELLOW	WHITE-STP BR	6.0
5TH STREET (S OF IL 84)														
ENTIRE SIDEROAD														
8 + 35 - 9 + 87					830.2		709.1	830.2	541.0			YELLOW	WHITE-STP BR	7.7
3RD STREET (S OF IL 84)														
109 + 73				131.6			89.9	131.6	98.0			YELLOW		1.3
6TH STREET (S OF IL 84)														
121 + 44						152.7	208.8	152.7	135.6			YELLOW		1.3
TOTALS	54.7	115.4		4115.3				4266.4	1147.0	1643.0		1893.0		210.3

- * SEE SPECIAL PROVISION
- ** ADDITIONAL BITUMINOUS PRIME COAT IS ON THE ENTRANCE SCHEDULE
- *** ADDITIONAL INCIDENTAL BITUMINOUS SURFACING IS ON SCHEDULE OF QUANTITIES AND ENTRANCE SCHEDULE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. _____ HORIZ. _____

DATE _____

DRAWN BY _____

CHECKED BY _____

PLOT DATE = Wed Feb 09 10:37:02 2005
 FILE NAME = C:\p\projects\228584\228584.dgn
 PLOT SCALE = 1/8" = 1' / IN.
 REFERENCE = WEP