

ENTRANCE SCHEDULE

CONTRACT NO. 64A10

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & TS	HENRY	90	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	REMARKS		DRIVEWAY WIDTH FOOT	FLARE WIDTH FOOT	APRON LENGTH FOOT	APRON SECTION AREA SQ. YARD	RUN LENGTH BIT FOOT	ADDL. DRVWY AREA BITUMINOUS SQ YARD	TOTAL AGGREGATE AREA SQ YARD	TOTAL CONCRETE AREA SQ YARD	TOTAL BITUMINOUS AREA SQ YARD	40600200	35101400	X4080020	42300300	44000200	
												* BIT PRIME COAT TONS	**AGG BASE CSE T-B TONS	***2" INC BIT SURF SUPER, N50 TONS	PCC DRIVEWAY PAVEMENT 7" SQ YD	DRVWY PVMNT REM SQ YD	
IL 84		Proposed															
109+97	PE	RT	BIT W/CONC APR	35.0	65.0	15.0	82.9	20.3	57.5	62.7	82.9	57.5	0.082	28.58	6.44	82.9	167.7
111+97	CE	LT	BIT W/CONC APR	30.0	60.0	15.0	75.0	19.4	62.9	67.6	75.0	62.9	0.090	30.82	7.05	75.0	133.6
115+92	CE + MB	RT	BIT W/CONC APR	35.0	114.5	15.0	103.4	5.4	21.4	22.6	103.4	21.4	0.031	10.30	2.40	103.4	209.9
119+32	CE	LT	BIT W/CONC APR	35.0	65.0	15.0	83.3	19.4	74.3	78.5	83.3	74.3	0.106	35.78	8.33	83.3	204.0
120+34	CE	RT	BIT.	35.0	59.0	12.0	62.7	3.0	11.7	78.8	-	74.3	0.106	35.89	8.33	-	194.7
122+31	PE	RT	CONC.	14.6	39.0	12.0	36.0	7.0	-	-	47.7	-	-	-	-	47.7	89.2
125+00	CE	RT	CONC.	35.0	58.9	12.0	62.6	15.7	-	-	123.7	-	-	-	-	123.7	-
5TH ST.																	
8+62	CE	RT	BIT W/ CONC APR	24.0	50.2	15.0	64.1	8.0	91.3	91.3	64.1	91.3	0.131	41.59	10.22	64.1	198.5
8+90	CE	LT	BIT W/ CONC APR	42.6	64.6	16.8	124.9	-	67.2	67.2	124.9	67.2	0.096	30.60	7.52	124.9	338.7
9+35	CE	RT	BIT W/ CONC APR	22.0	41.3	15.0	46.1	15.0	47.5	47.5	46.1	47.5	0.068	21.62	5.32	46.1	96.1
10+68	CE	RT	CONC	24.0	50.6	15.0	61.5	-	-	-	108.2	-	-	-	-	108.2	-
10+77	CE	LT	BIT W/CONC APR	16.0	43.9	15.0	50.4	-	85.6	87.7	50.4	85.6	0.122	39.95	9.59	50.4	254.5
TOTALS										603.9	909.8	582.0	0.8	275.1	65.2	909.8	1886.7

*ADDITIONAL BITUMINOUS PRIME COAT IS ON THE BITUMINOUS SCHEDULE

**ADDITIONAL AGGREGATE BASE COURSE, TYPE B IS ON THE SCHEDULE OF QUANTITIES

***ADDITIONAL INCIDENTAL BITUMINOUS SURFACING IS ON THE SCHEDULE OF QUANTITIES AND BITUMINOUS SCHEDULE

PLOT DATE = Mon, Oct 11, 14, 2010 2:08:58
 FILE NAME = C:\temp\p101\20101011\20101011.dgn
 PLOT SCALE = 3/8" = 1' / IN.
 REFERENCE = #REF#

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. / HORIZ. DATE: _____ DRAWN BY: _____ CHECKED BY: _____