

DRAINAGE SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	(2R) M & TS	HENRY	90	25
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

XX146400 60255500 60500040 60500060 60500065 550A0050 550A0340 550A0120 550A0410 60107600 X0322033

LOCATION	OFFSET FT.	STORM SEWER REM FT.	MH TO BE ADJ. EACH	REM MH EACH	REM INLETS EACH	REM INLETS, SPECIAL EACH	STORM SEWER CLA T1 12" FT.	STORM SEWER CLA T2 12" FT.	STORM SEWER CLA T1 24" FT.	STORM SEWER CLA T2 24" FT.	* PIPE UNDER DRAINS 4" FT.	STORM SEWER (WATER MAIN REQ) 12" FT.
5TH STREET- REMOVAL AND ADJUST												
LT 8+53	18.3					1						
RT 8+55	19.8					1						
RT 8+76	17.2			1								
AR RT 8+76 TO LT 9+15		51										
RT 9+13	28.5			1								
LT 9+15	15.4			1								
LT 9+15 TO LT 9+62		63										
LT 9+25	11.8		1									
5TH STREET - NEW												
AR LT 8+42 (30) TO RT 8+42 (31)												24
RT 8+42 (31) TO RT 9+00 (32)												54
RT 9+13 (33) TO RT 9+00 (32)												11
RT 9+00 (32) TO RT 177+56 (15A)												57
LT 8+72 (34A) TO LT 9+23 (34A)												
LT 9+23 (34A) TO LT 9+38 (34)												
LT 9+38 (34) TO LT 118+14 (15)												25
AR LT 11+19 (35) TO RT 11+19 (36)							26					
RT 11+19 (36) TO RT 117+54 (11)							77					
TOTALS		313	1	4	1	2	626	729	184	50	108	560

* RT SIDE OF ROAD UNDER WIDENING

**ELBOW SHALL BE INCLUDED IN THE COST OF THE CMP

PLOT DATE = Mon Apr 11 14:35:13 2005
 FILE NAME = C:\p\projects\2005\64A\64A.dwg
 PLOT SCALE = 50.0000' / IN.
 REFERENCE = NONE