## **General Notes**

The contractor shall submit four copies of the required shop drawings for review and approval to the Bureau of Bridges and Structures, 2300 South Dirksen Parkway, Springfield, IL 62764. After approval of initial submittal, the contractor shall submit one set of shop drawings to Eric Harm, Engineer of Materials, 126 East Ash Street, Springfield, IL 62706, and eight (8) sets of shop drawings to be distributed to:

District 2 District Engineer (1) Fabricator (1) Contractor (2) Resident Engineer (2) District 2 Bureau of Materials (2)

Work on this project will be in progress at the same time as work on the ROCKFORD BYPASS US 20 (BYP). Work on these projects shall be scheduled to keep interference between all the projects to a minimum. The contractors shall inform each other of progress of the projects and give fair warning to the other contractors when a problem might be encountered.

A contingency item of 10 delineators is included to delineate potential hazards in the project limits. These to be placed upon project completion at the discretion of the engineer.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Mr. Frank Rose

2404 Eigth Ave.

Rockford IL 61108

Mr. Scott Stogsdill

1844 Ferry Road

Naperville IL 60563-9600

NICOR Gas Co.

Telephone

630-983-8676 ,

SBC/Ameritech Telephone Co. 815-394-7276

Mr.	Mike	Lenox

Commonwealth Edison Company 815-490-2869

123 Energy Ave. Rockford IL 61109

Mr. Kalin Hinshaw

Verizon 112 West Elm Street Sycamore IL 60178

815-895-1515

Mr. Scott Schroeder CATV 815-284-2257 Insight Communications

115 N. Galena Ave Dixon IL 61021

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

Mr. Dennis Schultz IDOT - Dist. 2

815-284-5469

819 Depot Ave Dixon IL 61021

## **Summary Of Quantities**

Code Number	Pay Item	Unit	Quantity
			SFTY-2A
50102400	CONCRETE REMOVAL	CU YD	20.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	20.9
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	39090
50501110	STRUCTURAL STEEL REMOVAL	POUND	23300
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4370
58100100	WATERPROOF MEMBRANE REPAIR	SQ YD	52
63500105	DELINEATORS	EACH	10
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100410	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416	EACH	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	12796
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5290
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4287.5
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	700
78300100	PAVEMENT MARKING REMOVAL	SQ FT	145
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	6
Z0022400	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	78

\* SPECIALTY ITEM

The following Mixture Requirements are applicable for this project:

Mixture Uses(s):	Surface	1	¥	
PG:	SBS 70-22			
RAP%: (Max)	0%			
Design Air Voids				
Mixture Composition	II 9.5 or 12.5			
(Gradation Mixture)	12 3.3 01 12.3			
Friction Aggregate	E			
20 Year ESAL				

Structure No. 101-0133 I-39 over Kishwaukee River Winnebago County FAI Route 39 Section 201-1B-M-2