

CONTRACT #66338

MAINLINE BITUMINOUS SCHEDULE													
LOCATION		LENGTH	WIDTH (PROP)	BIT MATERIALS PR CT	AGG PR CT	MIX FOR CRACKS, JOINTS FLANGEWAYS	LEVEL BINDER (HM) SUPERPAVE	BIT CONC SURF CSE SUPERPAVE	AGG SHLD TY B	BIT SURF REM 3/4"	BIT SURF REM 1 1/4"	BIT SURF REM BUTT JT	TEMP RAMP
		FEET	FEET	GAL	TON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
1080+27 TO 1080+57		30	24	6	0.2	0.02	0.04	6.7	2			80	13.3
1080+57 TO 1119+74		3917	24	836	20.9	3.13	5.22	877.4	260.2	10445			
1119+74 TO 1120+04		30	24	6	0.2	0.02	0.04	6.7	2			80	13.3
1120+04 TO 1120+30	SN 038-0038 (OMIT)	26	34.9										
1120+30 TO 1120+60		30	24	6	0.2	0.02	0.04	6.7	2			80	13.3
1120+60 TO 1172+76		5216	24	1113	27.8	4.17	6.95	1168.4	346.5	13909			
1172+76 TO 1173+06		30	24	6	0.2	0.02	0.04	6.7	2			80	13.3
1173+06 TO 1173+54	SN 038-0039 (OMIT)	48	38										
1173+54 TO 1173+84		30	24	6	0.2	0.02	0.04	6.7	2			80	13.3
1173+84 TO 1250+33.8		7649.8	24	1632	40.8	6.12	10.2	1713.6	508.2	20399			
1250+33.8 TO 1250+63.8		30	24	6	0.2	0.02	0.04	6.7	2			80	
1250+63.8 TO 1251+06.2	SN 038-0040	42.4	38.5	15	0.4	0.05	0.09	12.7				181	
1251+06.2 TO 1251+36.2		30	24	6	0.2	0.02	0.04	6.7	2			80	
1251+36.2 TO 1293+89		4252.8	24	907	22.7	3.4	5.67	952.6	282.5	11341			
1293+89 TO 1294+19		30	24	6	0.2	0.02	0.04	6.7	2			80	13.3
TOTALS				4551	114.2	17.03	28.45	4778.3	1413.4	56094	341	480	79.8

NOTE: THE EXISTING AGGREGATE SHOULDERS ARE LOW. ADDITIONAL QUANTITY OF AGGREGATE SHOULDER, TYPE B HAS BEEN ADDED.

SEEDING SCHEDULE						
SIDEROAD	CL 2 SEEDING	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	EROSION CONTROL BLANKET	FURNISHED EXCAVATION
	ACRE	POUND	POUND	POUND	SQ YD	CU YD
NORTH ST. WEST	0.01	0.9	0.9	0.9	41.9	0.4
NORTH ST. EAST	0.01	0.9	0.9	0.9	41.9	0.4
LOCUST ST. EAST	0.01	0.9	0.9	0.9	41.9	0.4
WASHINGTON ST. EAST	0.01	0.9	0.9	0.9	41.9	0.4
JEFFERSON ST. WEST	0.01	0.9	0.9	0.9	41.9	0.4
2100 N WESTBOUND	0.01	0.9	0.9	0.9	41.9	0.4
2100 N EASTBOUND	0.01	0.9	0.9	0.9	41.9	0.4
2000 N WESTBOUND	0.01	0.9	0.9	0.9	41.9	0.4
2000 N EASTBOUND	0.01	0.9	0.9	0.9	41.9	0.4
1900 N WESTBOUND	0.01	0.9	0.9	0.9	41.9	0.4
1900 N EASTBOUND	0.01	0.9	0.9	0.9	41.9	0.4
1850 N EASTBOUND	0.01	0.9	0.9	0.9	41.9	0.4
E 3RD ST. WEST	0.01	0.9	0.9	0.9	41.9	0.4
E 2ND ST. WEST	0.01	0.9	0.9	0.9	41.9	0.4
TOTALS	0.14	12.6	12.6	12.6	586.6	5.6

OMISSIONS
 STA 1120+04 TO 1120+30
 STA 1173+06 TO 1173+54

3/31/2005 c:\projects\ed02603\defal1.s.dgn