

80% FED  
20% STATE

80% FED  
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 1000	STRUCTURE NO. 050-W001 Y007	STRUCTURE NO. 050-C803 Y007	STRUCTURE NO. 050-W003 Y007	STRUCTURE NO. 050-W002 Y007
20100110	TREE REMOVAL 6 TO 15 UNITS DIAMETER	UNIT	317	317				
20100210	TREE REMOVAL OVER 15 UNITS DIAMETER	UNIT	122	122				
20101100	TREE TRUNK PROTECTION	EACH	17	17				
20200100	EARTH EXCAVATION	CU. YD.	290	290				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU. YD.	67	67				
20400800	FURNISHED EXCAVATION	CU. YD.	210	210				
20800150	TRENCH BACKFILL	CU. YD.	11	11				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	58	58				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	58	58				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	58	58				
25100115	MULCH, METHOD 2	ACRE	0.64	0.64				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	840	840				
28000400	PERIMETER EROSION BARRIER	FOOT	1072	1072				
28000500	INLET AND PIPE PROTECTION	EACH	4	4				
28100107	STONE RIPRAP, CLASS A4	SQ. YD.	16	16				
28200200	FILTER FABRIC	SQ. YD.	16	16				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	46	46				
42001200	PAVEMENT FABRIC	SQ. YD.	16	16				
42001300	PROTECTIVE COAT	SQ. YD.	75	75				
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ. YD.	421	421				
44001900	COMBINATION CURB & GUTTER REMOVAL (SPECIAL)	FOOT	150	150				
44200924	CLASS B PATCHES, TYPE III, 7 INCH	SQ. YD.	16	16				
44213200	SAW CUTS	FOOT	48	48				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	50	50				

\* SPECIALTY ITEM

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 1000	STRUCTURE NO. 050-W001 Y007	STRUCTURE NO. 050-C803 Y007	STRUCTURE NO. 050-W003 Y007	STRUCTURE NO. 050-W002 Y007
48202210	BITUMINOUS SHOULDERS SUPERPAVE 4 1/2"	SQ. YD.	40	40				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1	
50102400	CONCRETE REMOVAL	CU. YD.	2.5	0.5		2.0		
50200100	STRUCTURE EXCAVATION	CU. YD.	433		135	17	85	196
50200400	ROCK EXCAVATION FOR STRUCTURES	CU. YD.	5			5		
50300225	CONCRETE STRUCTURES	CU. YD.	148		41.8	26.0	27.7	52.5
50300510	RUSTICATION FINISH	SQ. FT.	2858		980		643	1235
50500505	STUD SHEAR CONNECTORS	EACH	490		166		104	220
50700209	UNTREATED TIMBER LAGGING	SQ. FT.	2256		776		512	968
X5120902	FURNISHING SOLDIER PILES (HP 14X73)	FOOT	438				158	280
X5120903	FURNISHING SOLDIER PILES (HP 14X117)	FOOT	321		281		40	
X5120910	FURNISHING SOLDIER PILES (W14X159)	FOOT	132					132
50800105	REINFORCEMENT BARS	POUND	5620			5620		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16200		3900		5320	6980
51500100	NAME PLATES	EACH	4		1	1	1	1
54213450	END SECTIONS 15"	EACH	1	1				
542C3421	PIPE CULVERT, CLASS C, TYPE 5 66"	FOOT	196			196		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	48	48				
55100500	STORM SEWER REMOVAL 12"	FOOT	25	25				
59100100	GEOCOMPOSITE WALL DRAIN	SQ. YD.	183		63		43	77
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1	1				

\* SPECIALTY ITEM

SUMMARY OF QUANTITIES

IL ROUTE 71  
OVER TRIBUTARY TO ILLINOIS RIVER  
F.A.P. ROUTE 627 - SEC. (1-1)I-1  
LA SALLE COUNTY