

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: X181-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	682
50102400	CONCRETE REMOVAL	CU YD	32.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	32.3
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	220
50500725	JACK AND REPLACE BEARINGS	EACH	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7463
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1914
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	632
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1144
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1144
** 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1914
** 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	50
78300100	PAVEMENT MARKING REMOVAL	SQ FT	632
XZ191205	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 3"	SQ YD	682
X0321468	PLUG EXISTING DECK DRAINS	EACH	8
X0322379	CONCRETE SEALER	SQ YD	93
XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	100
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
Z0002600	BAR SPLICER	EACH	28
Z0006205	BRIDGE DECK HYDRO-SCARIFICATION 1 1/2"	SQ YD	682
Z0015595	DECK DRAIN EXTENSIONS	EACH	24
* Z0030250	IMPACT ATTENUATOR, TEMPORARY, NON-REDIRECTIVE, TEST LEVEL 3	EACH	1
* Z0030350	IMPACT ATTENUATOR, RELOCATE, NON-REDIRECTIVE, TEST LEVEL 3	EACH	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	59
X0322905	PPC I BEAM REPAIRS	L SUM	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 S.N. 050-0168 (NB)
 F.A.I. 412 OVER C. & N.W. RAILROAD
 SECTION (50-GVB)I-1
 STA. 1429+12.74

MARCH 21, 2005
 C:\PROJECTS\CMA IN06\CM30\DETAILS.DGN

*SFTY-3N **SPECIALTY ITEMS