

CONTRACT NO. 66669				
F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
412	(50-GVB)I-1	LASALLE	25	3
FED. ROAD DIST. NO.		ILLINOIS	STATE AID PROJECT	

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: X181-2A

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
42001510	PC CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT (SPECIAL)	SQ YD	12
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)	SQ YD	682
50102400	CONCRETE REMOVAL	CU YD	33.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	33.0
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	59
50500725	JACK AND REPLACE BEARINGS	EACH	12
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7326
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100305	TRAFFIC CONTROL AND PROTECTION, STANDARD 701400	L SUM	1
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1914
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	632
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1144
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1144
** 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	1914
** 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	50
78300100	PAVEMENT MARKING REMOVAL	SQ FT	632
XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	100
XZ191205	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 3"	SQ YD	682
X0301878	BRIDGE APPROACH SHOULDER REMOVAL, SPECIAL	SQ YD	12
X0321468	PLUG EXISTING DECK DRAINS	EACH	8
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	97
X0322379	CONCRETE SEALER	SQ YD	93
X0322905	PPC I BEAM REPAIRS	L SUM	1
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
Z0002600	BAR SPLICER	EACH	28
Z0006205	BRIDGE DECK HYDRO-SCARIFICATION 1 1/2"	SQ YD	682
Z0015595	DECK DRAIN EXTENSIONS	EACH	24
* Z0030250	IMPACT ATTENUATOR, TEMPORARY, NON-REDIRECTIVE, TEST LEVEL 3	EACH	1
* Z0030350	IMPACT ATTENUATOR, RELOCATE, NON-REDIRECTIVE, TEST LEVEL 3	EACH	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

* SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
S.N. 050-0167 (SB)
F.A.I. 412 OVER C. & N.W. RAILROAD
SECTION (50-6VB)I-1
STA. 1429 + 12.74

DATE - MARCH 06, 2005
 DGN - CMOS/CM327/DETAILS.DGN