

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	53
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		


TEMPORARY EROSION CONTROL SCHEDULE												
LOCATION	STA	TO	STA	LENGTH M	WIDTH M	AREA (CADD CALCS) SQ M	TEMPORARY EROSION CONTROL SEEDING KG	SEEDING CLASS 7 HA	MULCH, METHOD 2 HA	EROSION CONTROL BLANKET SQ M	EROSION CONTROL BARRIER M	FENCE (EROSION CONTROL) M
STAGE 3							4 app at 110kg/Ha					
MAINLINE												
WAR MEM DRIVE	38+965.070	TO	39+150.000	184.93								
	39+150.000	TO	39+500.000	350.00								
	39+500.000	TO	39+850.000	350.00								170.00
	39+850.000	TO	40+175.000	325.00								120.00
	40+175.000	TO	40+480.82	305.82								
			WAR MEM DR SUBTOTAL:				0.00	0.00	0.00	0.00	0.00	290.00
SCENIC DRIVE	10+050.000	TO	10+288.277	238.77								
MALL ACCESS	9+936.557	TO	9+986.557	50.00								
BRANDYWINE DR	39+385.798	TO	39+458.410	80.00								
GLEN AVENUE	101+038.000	TO	101+181.340	143.34								
STERLING AVE	100+910.908	TO	100+970.889	80.00								
			STAGE 3 SUBTOTAL:				0	8	8	12	0	2,350

Prior to beginning Earthwork or structure removal perimeter erosion barrier shall be placed in accordance with the typical application of silt filter fence detail and section 280 of the Standard Specifications for Road and Bridge Construction and as directed by the Engineer.

Temporary ditch checks shall be placed immediately upon disturbance of existing slopes in accordance with the temporary erosion control Special provisions and Section 280 of the Standard Specifications for Road and Bridge Construction and as directed by the Engineer.

WB 1-74 SUBTOTAL:								1.8	1.8	12		1,615
RAMPS SUBTOTAL:								6.6	6.6			445
WAR MEM DR SUBTOTAL:												290
SCENIC DR SUBTOTAL:												
MALL ACCESS SUBTOTAL:												
BRANDYWINE DR SUBTOTAL:												
GLEN AVE SUBTOTAL:												
STERLING AVE SUBTOTAL:												
TOTAL								8.5	8.5	12		2,350
TOTAL FOR 1000-2A												290
TOTAL FOR 0000-2A								8.5	8.5	12		2,060

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION TEMPORARY EROSION CONTROL SCHEDULE FAI ROUTE 74 (1-74) (WB)
NAME	DATE	



DRAWN BY CADD
CHECKED BY RSC
DATE 11/12/04