



PROPOSED TYPICAL SECTION #22

WB STA. 146+117.000 TO STA. 146+125.000 (FULL SUPER)



PROPOSED TYPICAL SECTION #23

WB STA. 146+125.000 TO STA. 146+406.380 (FULL SUPER)



PROPOSED TYPICAL SECTION #24

WB STA. 146+406.380 TO STA. 146+410.000 (FULL SUPER)

NOTES:

- 1. MEDIAN PIPE UNDERDRAINS TO BE DRAINED TO MEDIAN STORM SYSTEM.
- 2. OFFSET PIPE UNDERDRAINS TO AVOID CONFLICTS WITH BRIDGE, LIGHTING FOUNDATION, AND DRAINAGE STRUCTURE ELEMENTS.
- 3. SEE SUPERELEVATION TRANSITION DETAILS FOR ADDITIONAL CROSS SLOPE INFORMATION.
- 4. QUANTITIES FOR AGG. SUBBASE, 300 mm MIN. WHERE SHOWN TO VARY TIEING INTO EXISTING AGG. SUBBASE ARE INCLUDED IN THE QUANTITY CALCULATIONS.

LEGEND

- (50) PROPOSED GROUND LINE
- PR GEOTECHNICAL FABRIC FOR GROUND STABILIZATION
- (56A) PR FURNISH AND PLACE TOP SOIL 100 mm
- (59A) PR SUB-BASE GRANULAR MATERIAL, TYPE A 150 mm
- (60) PR AGGREGATE SUBBASE, 300 mm MIN.
- PR BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19,OL (LOW ESAL), 150 mm
- PR CONTINUOUSLY REINFORCED PORTLAND CEMENT 75 PR CONTINUOUSET NEWS ... CONCRETE PAVEMENT 290 mm
- (79) PR AGGREGATE SHOULDERS, TYPE B
- (81B) PR PORTLAND CEMENT CONCRETE SHOULDERS 290 mm
- (81C) PR PORTLAND CEMENT CONCRETE SHOULDERS 200 mm
- (86A) PR PIPE UNDERDRAINS 100 mm
- (88) PR CONCRETE GUTTER, TYPE A (MODIFIED)
- (96A) PR LONGITUDINAL CONSTRUCTION JOINT
- (968) PR SAWED LONGITUDINAL JOINT

STRUCTURAL DESIGN TRAFFIC:

Year 2025 MU = 5%

PV = 90% SU = 5%

ROAD/STREET CLASSIFICATION: CLASS I

PERCENT OF STRUCTURAL DESIGN TRAFFIC IN DESIGN LANE:

S = 45% M = 45% TRAFFIC FACTOR: ACTUAL TF = 38.28

MINIMUM TF = 7.54

SUBGRADE SUPPORT RATING: POOR

		١ ١
RS, INC.		DATE

NAME

ILLINOIS DEPARTMENT OF TRANSPORTATION

TYPICAL SECTIONS FAI ROUTE 74 (I-74) WB STA. 146+117.000 TO 146+410.000

DRAWN BY CAM CHECKED BY LSA 11/23/04