 F.A.I. RTE.	SECTION	SECTION COUNTY		SHEE'
74	(72-7)R-3	PEORIA	1360	1187
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED.	AID PROJ	ECT

CONTRACT NO. 68200


EXISTING CONCRETE INSERT

UNDERPASS LUMINAIRE, HPSV, S-C-I, 100WATT, 240VOLT (SEE DETAIL SHT. 46)


EXISTING BOLLARD (SEE PROJECT STANDARDS 504001A-174 AND 504002A-174)

- GROUND: GREEN (SIZE AS INDICATED ON PLANS) - NEUTRAL: WHITE (SIZE AS INDICATED ON PLANS) - PHASE: RED (SIZE AS INDICATED ON PLANS) PHASE: BLACK (SIZE AS INDICATED ON PLANS)

PROPOSED ST. LT. CABLE IN CONDUIT



PROPOSED LT. TOWER CALL-OUT



PROPOSED CONDUIT CALL-OUT

LIGHTING SHEET 3 OF 64

	REVISIONS			
	NAME	DATE	ILLINOIS DEPARTMENT	OF TRANSPORTATION
			ELECTRICAL	LEGEND
			•	
alfred benesch & company				
CONSULTING ENGINEERS				DRAWN BY DJK
205 NORTH MICHIGAN AVENUE, CHICAGO, ILLINOIS 60601			DATE: 11/12/04	CHECKED BY MKR

*	PROPOSED HIGH MAST POLE: SEE SCHEDULE ON LIGHTING SHTS. 5 & 6	
	PROPOSED HIGH MAST LUMINAIRE(S), DIRECTION OF ARROW INDICATES STREET SIDE: SEE SCHEDULE ON LIGHTING SHTS. 5 & 6	
	EXISTING HIGH MAST LUMINAIRE(S), DIRECTION OF ARROW INDICATES STREET SIDE	
	PROPOSED STREET LIGHT CONTROLLER.	
-	PROPOSED ELECTRICAL SERVICE INSTALLATION: SEE LIGHTING SHT. 39	
0	PROPOSED JUNCTION BOX	
●——● _{B(3)}	PROPOSED STREET LIGHTING UNIT: 13.5M M.H., TRANSFORMER BASE, 2.4M DAVIT ARM, 400W HPS, 240V MSIII LUMINAIRE TO BE INSTALLED IN STAGE 3.	
•—• C(3)	PROPOSED STREET LIGHTING UNIT: 13.5M M.H., 2.4M DAVIT ARM, 400W HPS, 240V MSIII LUMINAIRE TO BE INSTALLED IN STAGE 3.	
●	F PROPOSED COMBINATION POLE AND LUMINAIRE BY OTHERS	
	PROPOSED EMBEDDED CONDUIT, 75mm PVC SCHEDULE 40, UNLESS OTHERWISE NOTED	
	PROPOSED ATTACHED CONDUIT, 25mm GALVANIZED	
\longrightarrow	PROPOSED LIQUID-TIGHT FLEXIBLE CONDUIT, 25mm GALVANIZED	
%	EXISTING HIGH MAST POLE	
0	EXISTING JUNCTION BOX	
\boxtimes	EXISTING LIGHTING CONTROLLER	
	EXISTING ELECTRIC SERVICE INSTALLATION	
	EXISTING STREET LIGHT UNIT TO REMAIN	
o—○ x	X EXISTING LIGHT UNIT TO BE REMOVED	
◯ X(3)	X(3) EXISTING TEMPORARY WOOD POLE WITH LUMINAIRE TO BE REMOVED IN STAGE 3.	
(3)	EXISTING TEMPORARY WOOD POLE TO BE REMOVED IN STAGE 3.	
Д	EXISTING TEMPORARY AERIAL ST. LT. CABLE, 3-1/C *6 WITH GROUNDED MESSENGER TO BE REMOVED	

MESSENGER TO BE REMOVED

EXISTING CONDUIT TO REMAIN

EXISTING UNDERGROUND CABLE TO BE REMOVED

...\111000 7a_legend.dgc 11712/2004 4 13:05 PM