BILL OF MATERIALS - TEMPORARY SIGNING (SHEET 2 OF 5)

COUNTY TOTAL SHEET NO.
TAZEWELL 1366 341 SECTION FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

*(90-11)R-2;90(13, 14, 14-1)R-1

*L1 IS THE POST CLOSEST TO THE ROADWAY EDGE OF PAVEMENT

**
FOR INFORMATION ONLY
ITEM INCLUDED IN TEMPORARY SIGN ITEMS

 \triangle

				0.000												
LOCATION	STATION		MENSIONS	COMPOSITE TEMPORARY SIGN OVERLAY	PANEL OVERLAY	WOOD : SUPP(* *	SIGN DRT	CONCRETE FOUNDATIONS FOR WOOD SIGN SUPPORT ** (EACH)	MOUN	NTING	REINSTALL TEMP SIGN PANEL	RELOCATE SIGN PANEL ASSEMBLY TYPE B (EACH)	TEMP SIGN PANEL ASSEMBLY	LEGEND	SIGN DETAIL	COMMENTS
		HEIGHT	WIDTH (mm)	(SQ m)	(SQ m)	* L1 (m)	12 (m)	* * (FACH)	HT. ABOVE	OFFSET FROM E/P (m)	ASSEMBLY (EACH)	(EACH)	(SQ m)			
		V 138117	V 118112			L1 (1117)		V EAOII7			(EXOT)					
CAMP ST. STAGE 3A																
RT	2+141	305	610										0.2	TO		TSPA
RT		305	610			4.4		1	1.8	4.0			0.2	EAST	4	TSPA
RT RT		610 381	610 533										0. 2	I - 74 ◆•		TSPA TSPA
RT	2+301	305	610										0. 2	₹		TSPA
RT	2+301	305	610			4. 4		1	1.8	4.0			0.2	EAST	5	TSPA TSPA
RT RT		610 381	610 533										0.4	I - 74		TSPA
FVI	2/301	301	333										0. 2			1374
MAIN ST.											-					
STAGE 3A	2+175	600	750										0.5	WORK ZONE		TSPA
RT			600										0.5	SPEED LIMIT 40	9	TSPA
RT	2+175	305	610			5.2		1	1.8	4. 0			0.2	BEGINS	9	TSPA
RT		450	1000										0.5	\$XXX FINE MINIMUM		TSPA
RT RT	2+198 2+198	381 305	533 610			4.1		1	1.8	4.0			0.2	JCT EAST	8	TSPA TSPA
	2+198	610	610			4.1		.1	1.0	4.0			0.2	I-74	· ·	TSPA
		010											<u> </u>			
	-															
			-	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~												
												:				
	<u> </u>													•		
														· -		
							-									
	 															
									-							
	 															
SUBTOTAL SHE	ET 2 OF !)				* * 28.	. 3	** 6					4.5		•	

TSPA = TEMPORARY SIGN PANEL ASSEMBLY

-REVISED PAY ITEM -ADDED NOTE

T. I. S. SHEET 2 OF 33

REVISIONS
NAME DATE ILLINOIS DEPARTMENT OF TRANSPORTATION
A REVISED MAY 2.7 2005 FAI ROUTE 74 (I-74)

TEMPORARY GUIDE SIGN DETAILS

	├
TIRC	L
OIM	Г
URS CORPORATION	Г
DECATUR, ILLINOIS	

DATE 12-20-04

DRAWN BY RLS CHECKED BY JJM

 $(\dots,\dots,\dots,\dots,\dots)$

1. THE REMOVAL OF TEMPORARY SIGNING THAT IS INSTALLED WITHIN THIS CONTRACT IS INCLUDED WITHIN THE RESPECTIVE TEMPORARY SIGNING PAY ITEM.

2. THE REMOVAL OF TEMPORARY SIGN PANELS OR SIGN PANEL ASSEMBLIES THAT WERE PREVIOUSLY INSTALLED BY OTHERS IS PAID AS "REMOVE SIGN PANEL" OR "REMOVE SIGN PANEL ASSEMBLY" OF THE TYPE SPECIFIED.