

# SUMMARY OF QUANTITIES

|                       |               |         |                  |           |
|-----------------------|---------------|---------|------------------|-----------|
| P. A. D. NO.          | SECTION       | COUNTY  | TOTAL SHEETS     | SHEET NO. |
| 612                   | (109.110RS-1) |         | 40               | 4         |
| STA.                  |               | TO STA. |                  |           |
| FED. ROAD DIST. NO. 9 |               | ALWAYS  | FED. AID PROJECT |           |
| *FULTON & SCHUYLER    |               |         |                  |           |

| SUMMARY OF QUANTITIES |   |       | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE                        |   |  |  |  |
|-----------------------|---|-------|------------------|---|---|--|--|--|
| CODE NO               | ITEM  | UNIT  |                  | SCHUYLER COUNTY<br>1 000<br>80% FED/20% STATE | FULTON COUNTY<br>1 000<br>80% FED/20% STATE |  |  |  |
| 40600895              | CONSTRUCTING TEST STRIP   | EACH  | 1                | 0.06  | 0.94  |  |  |  |
| 40600980              | BITUMINOUS SURFACE REMOVAL - BUTT JOINT                         | SQ YD | 1096             | 74  | 1022  |  |  |  |
| 40600990              | TEMPORARY RAMP  | SQ YD | 141              | 12  | 129   |  |  |  |
| 40800020              | BITUMINOUS MATERIALS (PRIME COAT)                               | TON   | 56               | 4   | 52  |  |  |  |
| 40800030              | AGGREGATE (PRIME COAT)  | TON   | 281              | 18  | 263   |  |  |  |
| 40800040              | INCIDENTAL BITUMINOUS SURFACING                                 | TON   | 82               | 10  | 72  |  |  |  |
| 44000003              | BITUMINOUS SURFACE REMOVAL 3/4"                                 | SQ YD | 112497           | 8287  | 104210                                      |  |  |  |
| 44000006              | BITUMINOUS SURFACE REMOVAL 1 1/2"                               | SQ YD | 24205            |   | 24205                                       |  |  |  |
| 44201821              | CLASS D PATCHES, TY IV, 14"                                     | SQ YD | 311              |   | 311   |  |  |  |
| 48101200              | AGGREGATE SHOULDERS, TYPE B                                     | TON   | 1061             | 80  | 981   |  |  |  |
| 67100100              | MOBILIZATION  | L SUM | 1                | 0.06  | 0.94  |  |  |  |
| 70100455              | TRAFFIC CONTROL AND PROTECTION STD. 701206                      | L SUM | 1                |   | 1.00  |  |  |  |
| 70100460              | TRAFFIC CONTROL AND PROTECTION,<br>STANDARD 701306              | L SUM | 1                | 0.06  | 0.94  |  |  |  |
| 70300100              | SHORT-TERM PAVEMENT MARKING                                     | FOOT  | 10288            | 624   | 9664  |  |  |  |
| 70300625              | TEMPORARY PAINT PAVEMENT MARKING<br>LINE 4"                     | FOOT  | 162571           | 7700  | 154871                                      |  |  |  |
| 70301000              | WORK ZONE PAVEMENT MARKING REMOVAL                              | SQ FT | 1715             | 104   | 1611  |  |  |  |
| * 78001110            | PAINT PAVEMENT MARKING - LINE 4"                                | FOOT  | 162501           | 7700  | 154801                                      |  |  |  |
| * 78100100            | RAISED REFLECTIVE PAVEMENT MARKER                               | EACH  | 712              | 44  | 668   |  |  |  |
| 78300200              | RAISED REFLECTIVE PAVEMENT MARKER,<br>REMOVAL                   | EACH  | 712              | 44  | 668   |  |  |  |
| X4066424              | BITUMINOUS CONCRETE SURFACE COURSE, SUPER<br>PAVE, MIX "D", N50 | TON   | 11571            | 702   | 10869                                       |  |  |  |

\* SPECIALTY ITEMS