

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	138-21RS	MCDONOUGH	66	24
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**TEMPORARY & EPOXY PAVEMENT MARKING - LINE 4"**

STATION TO STATION	SOLID WHITE	SOLID YELLOW	SKIP-DASH YELLOW	DOUBLE YELLOW
LOCATION	FOOT	FOOT	FOOT	FOOT
<b>EDGELINES</b>				
NB RT STA 55+00 - 95+12.60	4012.6			
NB RT STA 96+40.39 - 141+02.87	4462.5			
NB LT STA 61+00 - 76+30.80		1530.8		
NB LT STA 78+31.55 - 89+90.53		1159.0		
NB LT STA 89+90.53 - 95+28.37		537.8		
NB LT STA 95+28.37 - 137+75.37		4247.0		
NB LT STA 137+75.37 - 141+02.87		327.5		
SB LT STA 56+84 - 71+00	1416.0			
SB LT STA 72+36.41 - 90+05.30	1768.9			
SB LT STA 90+94.38 - 95+00	405.6			
SB LT STA 97+20.72 - 141+02.87	4382.2			
SB RT STA 61+00 - 76+09.81		1509.8		
SB RT STA 78+19.40 - 96+70.68		1851.3		
SB RT STA 96+70.68 - 141+02.87		4432.2		
MEDIAN STA 61+00 - 76+00			760.0	
MEDIAN STA 76+09.81 - 78+31.55				922.8
STA 78+82.04 (NOSE)		91.6		
STA 90+26.78 (NOSE)		46.4		
STA 90+64.88 (NOSE)		101.5		
STA 95+69.86 (NOSE)		87.3		
STA 96+46.37 (NOSE)		83.7		
STA 111+89.98 (NOSE)		144.3		
STA 112+12.02 (NOSE)		147.1		
STA 127+81.93 (NOSE)		147.1		
STA 128+06.15 (NOSE)		153.1		
STA 137+85.35 (NOSE)		115.2		
STA 138+21.06 (NOSE)		134.0		
<b>SIDERoadS</b>				
NEW BURLINGTON ROAD	188.0			161.6
KROHE ROAD	155.8			
DOG POUND DRIVE	617.1			554.6
TOWER ROAD	527.7			301.3
<b>SUB-TOTALS</b>	17936.4	16846.7	760.00	1940.3
<b>TOTAL</b>	<b>37483.4</b>			

**TRAFFIC CONTROL & PROTECTION STANDARD 701401**

LOCATION	EACH
NORTHBOUND	2
SOUTHBOUND	2
<b>TOTAL</b>	<b>4</b>

**TRAFFIC CONTROL & PROTECTION**

LOCATION	L SUM
STANDARD 701400	1
STANDARD 701421	1
STANDARD 701422	1
STANDARD 701426	1
STANDARD 701602	1
STANDARD 701701	1

**TRAFFIC CONTROL SURVEILLANCE**

LOCATION	CAL DA
PROJECT LIMITS	20
<b>TOTAL</b>	<b>20</b>

**ENGINEERS FIELD OFFICE, TYPE A**

LOCATION	CAL MO
PROJECT LIMITS	2
<b>TOTAL</b>	<b>2</b>

**CHANGEABLE MESSAGE SIGN**

LOCATION	CAL DAYS
NB LANES	60
SB LANES	60
<b>TOTALS</b>	<b>120</b>

**MOBILIZATION**

LOCATION	L SUM
PROJECT LIMITS	1
<b>TOTAL</b>	<b>1</b>

PLOT DATE: 3/26/2005  
 FILE NAME: c:\p\projects\68334\plans.dgn  
 PLOT SCALE: 1/8"=1'-0"  
 USER: bmc

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: VERT. DATE  
HORIZ.

DRAWN BY  
CHECKED BY