

**SUMMARY OF QUANTITIES**

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1512	.	CHAMPAIGN	13	4

CONTRACT NO. 70471  
D5 CONTRACT MAINT 2005-14

LOCATION OF WORK:

FAS 1512 (US 150)

Sta. 301+48 to

Sta. 323+66

Sta. 354+83 to

Sta. 397+44

100% STATE  
RURAL TWO-LANE

CONSTRUCTION TYPE CODE:

1000  
TOTAL  
QUANTITY

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>1000 TOTAL QUANTITY</u>
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	432.0
40600300	AGGREGATE (PRIME COAT)	TON	9.0
40600990	TEMPORARY RAMP	SQ YD	27.0
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	8,639.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	108.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,178.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	196.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	8,099.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	83.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	83.0
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	726.0
X4401705	PARTIAL DEPTH REMOVAL	SQ YD	192.0
Z0004800	BITUMINOUS MIXTURE FOR PATCHING	TON	70.0

\* SPECIALITY ITEMS