

SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1512	*	CHAMPAIGN	13	9

CONTRACT NO. 70471
* D5 CONTRACT MAINT 2005-14

TEMPORARY RAMP - 40600990

STATION	DIRECTION	AREA
301+48	EASTBOUND	6.7
323+66	EASTBOUND	6.7
354+83	EASTBOUND	6.7
397+44	EASTBOUND	6.7
SUB-TOTAL =		26.7 SQ YD
FINAL TOTAL =		27.0 SQ YD

SCHEDULE FOR PARTIAL DEPTH PATCHING

PAINT PAVEMENT MARKING LINE. 4 INCH - 78001110

YELLOW

STATION	TO	STATION	LENGTH
301+48		323+66	554.5
354+83		397+44	1065.3
TOTAL =			1619.8 FT

WHITE

STATION	TO	STATION	LENGTH
301+48		323+66	2218.0
354+83		397+44	4261.0
TOTAL =			6479.0 FT
SUB-TOTAL =			8098.8 FT
FINAL TOTAL =			8099.0 FT

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	EXISTING OVERLAY THICKNESS (inch)	PARTIAL DEPTH REMOVAL X4401705 (sq. yd)	BIT MIX FOR PATCHING Z0004800 (Ton)
302+08	EASTBOUND	DL	25	12	3.5	33.3	12.1
305+81	EASTBOUND	DL	10	6	3.5	6.7	2.4
308+41	EASTBOUND	DL	6	12	3.5	8.0	2.9
309+32	EASTBOUND	DL	15	6	3.5	10.0	3.6
312+02	EASTBOUND	DL	4	12	3.5	5.3	1.9
313+22	EASTBOUND	DL	8	12	3.5	10.7	3.9
315+19	EASTBOUND	DL	30	6	3.5	20.0	7.3
318+33	EASTBOUND	DL	25	6	3.5	16.7	6.1
322+00	EASTBOUND	DL	10	6	3.5	6.7	2.4
322+36	EASTBOUND	DL	30	6	3.5	20.0	7.3
359+08	EASTBOUND	DL	10	6	3.5	6.7	2.4
362+08	EASTBOUND	DL	6	12	3.5	8.0	2.9
364+69	EASTBOUND	DL	6	12	3.5	8.0	2.9
378+28	EASTBOUND	DL	10	12	3.5	13.3	4.9
379+27	EASTBOUND	DL	8	12	3.5	10.7	3.9
380+92	EASTBOUND	DL	6	12	3.5	8.0	2.9
SUB-TOTALS =						192.0 (sq. yd)	69.9 (Ton)
FINAL TOTALS =						192.0 (sq. yd)	70.0 (Ton)