

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
325		MONTGOMERY	39	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• 21RS-4; 24RS-7				

RESURFACING

LOCATION	LENGTH	WIDTH	PR BIT SURF CSE AREA	AVERAGE THICKNESS	BITUMINOUS SURF. REM. (VAR. DEPTH)	BITUMINOUS SURF. REM. 40MM	BITUMINOUS SURF. REM. 60MM	BITUMINOUS SURF. REM. BUTT JOINT	TEMPORARY RAMPS	BIT MATLS (PRIME COAT) M4060200	AGGREGATE (PRIME COAT) M4060300	LEVEL. BIND. SUPER (19MM) N70	POLY BIT SURF SUPER MIX D N70 (38MM)
	METER	METER	SQ M	MM	SQ M	SQ M	SQ M	SQ M	SQ M	M TON	M TON	M TON	M TON
STA 4+015.000 TO STA 4+024.120 (RAMP)	9.120	11.14	101.60	38 TO 57	50.80	-	-	50.80	16.93	0.042	0.22	-	10.60
STA 4+024.120 TO STA 4+040.364	16.244	11.14	180.96	57	180.96	-	-	-	-	0.074	0.40	8.39	16.78
STA 4+040.364 TO STA 4+914.000	873.636	7.32	6395.02	57	6,395.02	-	-	-	-	2.622	14.07	296.47	592.95
STA 4+914.000 TO STA 4+923.140 (RAMP)	9.140	7.32	66.90	57	66.90	-	-	-	-	0.027	0.15	3.10	6.20
STA 4+923.140 TO STA 5+032.617	109.477	7.32	801.37	57	-	-	801.37	-	-	0.329	1.76	37.15	74.30
STA 5+032.617 TO STA 5+037.177 (RAMP)	4.560	7.32	33.38	57 TO 38	33.38	-	-	-	-	0.014	0.07	-	7.74
STA 5+037.177 TO STA 5+109.177	72.000	7.32 TO 10.80	652.32	38	-	652.32	-	-	-	0.267	1.44	-	60.48
STA 5+109.177 TO STA 5+224.974	115.797	10.80	1250.61	38	-	1,250.61	-	-	-	0.513	2.75	-	115.96
STA 5+224.974 TO STA 5+314.974	90.000	10.80 TO 7.32	815.40	38	-	815.40	-	-	-	0.334	1.79	-	75.60
STA 5+314.974 TO STA 5+319.534 (RAMP)	4.560	7.32	33.38	38 TO 57	33.38	-	-	-	-	0.014	0.07	-	3.87
STA 5+319.534 TO STA 6+005.500	685.966	7.32	5021.27	57	-	-	5,021.27	-	-	2.059	11.05	232.79	465.57
STA 6+005.500 TO STA 6+065.500	60.000	7.32 TO 10.98	549.00	57	-	-	549.00	-	-	0.225	1.21	25.45	50.90
STA 6+065.500 TO STA 6+180.000	114.500	10.98	1257.21	57	-	-	1,257.21	-	-	0.515	2.77	58.28	116.57
STA 6+180.000 TO STA 6+485.928	305.928	7.32	2239.39	57	-	-	2,239.39	-	-	0.918	4.93	103.82	207.64
STA 6+485.928 TO STA 6+758.035 (SE CORRECTION)	272.107	7.32	1991.82	57	1,991.82	-	-	-	-	0.817	4.38	92.34	184.68
STA 6+758.035 TO STA 7+039.050	281.015	7.32	2057.03	57	-	-	2,057.03	-	-	0.843	4.53	95.36	190.73
STA 7+039.050 TO STA 7+303.267 (SE CORRECTION)	264.217	7.32	1934.07	57	1,934.07	-	-	-	-	0.793	4.25	89.66	179.33
STA 7+303.267 TO STA 7+337.440	34.173	7.32	250.15	57	-	-	250.15	-	-	0.103	0.55	11.60	23.19
STA 7+337.440 TO STA 7+342.000 (RAMP)	4.560	7.32	33.38	57	-	-	-	33.38	11.13	0.014	0.07	-	3.87
BITUMINOUS SHOULDER AREAS (SEE SEPARATE SCHEDULE)					2,701.78	13,053.59	-	127.37	-	6.507	34.92	-	-
SIDEROAD AREAS (SEE SEPARATE SCHEDULE)					-	-	-	2,795.54	699.20	-	-	-	-
TOTAL =					13,388.1	15,771.9	12,175.4	3,007.1	727.3	17.0	91.4	1,054.4	2,387.0

ESTIMATED QUANTITIES

ITEMS	UNIT	SUB-TOTAL CITY
THE FOLLOWING ITEMS INCLUDE ESTIMATED QUANTITIES FOR PAVEMENT PATCHING		
PAVEMENT PATCHING, TYPE II, 375MM	SQ M	210
PAVEMENT PATCHING, TYPE III, 375MM	SQ M	65
CONC. CURB REPAIR	METER	150
BITUMINOUS SHOULDER REM. AND REPL. (SPECIAL)	SQ M	50

MANHOLES TO BE ADJUSTED

LOCATION STA.	QUANTITY (EACH)
4+040	1
4+045 (LT)	1
4+143 (RT)	1
4+145 (LT)	1
4+149 (LT)	1
4+340 (RT)	1
4+343 (LT)	1
4+345 (LT)	1
4+460 (LT)	1
4+551	1
4+553 (LT)	1
4+555 (RT)	1
4+559 (LT)	1
4+677 (LT)	2
4+787 (LT)	1
5+027 (RT)	1
5+245 (RT)	1
5+708 (RT) Shoulder	1
TOTAL =	19

WATER VALVES TO BE ADJUSTED

LOCATION STA.	QUANTITY (EACH)
STA. 4+240 LT	1
STA. 4+706 LT (WM)	1
STA. 4+909 LT	1
STA. 5+019 RT&LT	3
STA. 5+201 RT	1
STA. 5+205 LT	1
STA. 5+206 RT	1
STA. 5+686 RT	1
STA. 5+684 LT	1
STA. 6+234 LT	1
TOTAL =	12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULES**  
**SECTION : 24RS-4; 27RS-7**  
**MONTGOMERY COUNTY**

SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE