

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
325		MONTGOMERY	39	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• 21RS-4; 24RS-7				

BITUMINOUS SHOULDERS

LOCATION	LENGTH	BIT WIDTH	PR BIT SURF CSE AREA	AVERAGE THICKNESS	BITUMINOUS SURF. REM. (VAR. DEPTH)	BITUMINOUS SURF. REM. 40MM	BITUMINOUS SURF. REM. BUTT JOINT	BIT MATLS (PRIME COAT) M4060200	AGGREGATE (PRIME COAT) M4060300	BITUMINOUS SHOULDERS SUPER (VD)	BITUMINOUS SHOULDERS SUPER (38MM)
	METER	METER	SO M	MM	SO M	SO M	SO M	M TON	M TON	M TON	M TON
LT STA 4+015.000 TO LT STA 4+024.120 (RAMP)	9.12	2.44	22.3	57 TO 38	11.13	-	11.13	0.01	0.05	2.58	-
LT STA 4+024.120 TO LT STA 4+029.659	5.54	2.44	13.5	57 TO 38	13.52	-	-	0.01	0.03	1.57	-
LT STA 4+050.744 TO LT STA 4+130.654	79.91	1.83	146.2	57 TO 38	146.24	-	-	0.06	0.32	16.95	-
LT STA 4+147.287 TO LT STA 4+229.036	81.75	1.83	149.6	57 TO 38	149.60	-	-	0.06	0.33	17.34	-
LT STA 4+247.729 TO LT STA 4+329.632	81.90	1.83	149.9	57 TO 38	149.88	-	-	0.06	0.33	17.37	-
LT STA 4+353.269 TO LT STA 4+443.792	90.52	1.83	165.7	57 TO 38	165.66	-	-	0.07	0.36	19.20	-
LT STA 4+465.614 TO LT STA 4+537.603	71.99	1.83	131.7	57 TO 38	131.74	-	-	0.05	0.29	15.27	-
LT STA 4+564.984 TO LT STA 4+659.796	94.81	1.83	173.5	57 TO 38	173.51	-	-	0.07	0.38	20.11	-
LT STA 4+676.471 TO LT STA 4+774.829	98.36	1.83	180.0	57 TO 38	180.00	-	-	0.07	0.40	20.86	-
LT STA 4+793.373 TO LT STA 4+889.430	96.06	1.83	175.8	57 TO 38	175.78	-	-	0.07	0.39	20.37	-
LT STA 4+911.252 TO LT STA 4+914.000	2.75	3.05	8.4	57 TO 38	8.38	-	-	0.00	0.02	0.97	-
LT STA 4+914.000 TO LT STA 4+923.120 (RAMP)	9.12	3.05	27.8	57 TO 38	27.82	-	-	0.01	0.06	3.22	-
LT STA 4+923.120 TO LT STA 5+004.709	81.59	3.05	248.8	38	-	248.85	-	0.10	0.55	-	23.07
LT STA 5+027.888 TO LT STA 5+032.617	4.73	3.05	14.4	38	-	14.42	-	0.01	0.03	-	1.34
LT STA 5+032.617 TO LT STA 5+037.177 (RAMP)	4.56	3.05	13.9	38	-	13.91	-	0.01	0.03	-	1.29
LT STA 5+037.177 TO LT STA 5+109.177	72.00	3.05 TO 1.20	153.0	38	-	153.00	-	0.06	0.34	-	14.19
LT STA 5+109.177 TO LT STA 5+184.620	75.44	1.20	90.5	38	-	90.53	-	0.04	0.20	-	8.39
LT STA 5+228.417 TO LT STA 5+242.977	14.56	1.20	17.5	38	-	17.47	-	0.01	0.04	-	1.62
LT STA 5+242.977 TO LT STA 5+314.974	72.00	1.20 TO 3.05	153.0	38	-	152.99	-	0.06	0.34	-	14.19
LT STA 5+314.974 TO LT STA 5+319.534 (RAMP)	4.56	3.05	13.9	38	-	13.91	-	0.01	0.03	-	1.29
LT STA 5+319.534 TO LT STA 5+962.362	642.83	3.05	1960.6	38	-	1,960.63	-	0.80	4.31	-	101.79
LT STA 5+993.171 TO LT STA 6+235.142	241.97	3.05	738.0	38	-	738.01	-	0.30	1.62	-	68.43
LT STA 6+260.938 TO LT STA 6+485.928	224.99	3.05	686.2	38	-	686.22	-	0.28	1.51	-	63.63
LT STA 6+485.928 TO LT STA 6+758.035 (SE CORRECTION)	272.11	3.05	829.9	38	-	829.93	-	0.34	1.83	-	76.95
LT STA 6+758.035 TO LT STA 7+061.010	302.98	3.05	924.1	38	-	924.07	-	0.38	2.03	-	85.68
LT STA 7+061.010 TO LT STA 7+218.881 (SE CORRECTION)	157.87	3.05	481.5	38	-	481.51	-	0.20	1.06	-	44.65
LT STA 7+246.478 TO LT STA 7+281.307 (SE CORRECTION)	34.83	3.05	106.2	38	-	106.23	-	0.04	0.23	-	9.85
LT STA 7+281.307 TO LT STA 7+337.440	56.13	3.05	171.2	38	-	171.21	-	0.07	0.38	-	15.87
LT STA 7+337.440 TO LT STA 7+342.000 (RAMP)	4.56	3.05	13.9	38	-	-	13.91	0.01	0.03	-	1.29

PLOT DATE = 4/7/2006  
 FILE NAME = c:\prowork\4552918\vehshldr.dgn  
 USER NAME = ba

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES**

**SECTION : 24RS-4; 27RS-7**

**MONTGOMERY COUNTY**

SCALE: VERT. DATE:      HORIZ. DATE:      DRAWN BY:      CHECKED BY: