

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
325	•	MONTGOMERY	39	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• 21RS-4; 24RS-7				

BITUMINOUS SHOULDERS

LOCATION	LENGTH	BIT WIDTH	PR BIT SURF CSE AREA	AVERAGE THICKNESS	BITUMINOUS SURF. REM. (VAR. DEPTH)	BITUMINOUS SURF. REM. 40MM	BITUMINOUS SURF. REM. BUTT JOINT	BIT MATLS (PRIME COAT) M4060200	AGGREGATE (PRIME COAT) M4060300	BITUMINOUS SHOULDERS SUPER (VD)	BITUMINOUS SHOULDERS SUPER (38MM)
	METER	METER	SO M	MM	SO M	SO M	SO M	M TON	M TON	M TON	M TON
RT STA 4+015.000 TO RT STA 4+024.120 (RAMP)	9.12	2.44	22.3	57 TO 38	22.25	-	11.13	0.01	0.05	2.58	-
RT STA 4+053.061 TO RT STA 4+130.969	77.91	1.83	142.6	57 TO 38	142.57	-	-	0.06	0.31	16.52	-
RT STA 4+147.966 TO RT STA 4+228.898	80.93	1.83	148.1	57 TO 38	148.11	-	-	0.06	0.33	17.17	-
RT STA 4+248.165 TO RT STA 4+328.486	80.32	1.83	147.0	57 TO 38	146.99	-	-	0.06	0.32	17.04	-
RT STA 4+348.823 TO RT STA 4+542.142	193.32	1.83	353.8	57 TO 38	353.77	-	-	0.15	0.78	41.00	-
RT STA 4+561.370 TO RT STA 4+658.092	96.72	1.83	177.0	57 TO 38	177.00	-	-	0.07	0.39	20.51	-
RT STA 4+677.787 TO RT STA 4+775.326	97.54	1.83	178.5	57 TO 38	178.50	-	-	0.07	0.39	20.69	-
RT STA 4+792.961 TO RT STA 4+886.695	93.73	1.83	171.5	57 TO 38	171.53	-	-	0.07	0.38	19.88	-
RT STA 4+914.000 TO RT STA 4+923.120 (RAMP)	9.12	3.05	27.8	57 TO 38	27.82	-	-	0.01	0.06	3.22	-
RT STA 4+923.120 TO RT STA 5+002.089	78.97	3.05	240.9	38	-	240.86	-	0.10	0.53	-	22.33
RT STA 5+027.997 TO RT STA 5+032.617	4.62	3.05	14.1	38	-	14.09	-	0.01	0.03	-	1.31
RT STA 5+032.617 TO RT STA 5+037.177 (RAMP)	4.56	3.05	13.9	38	-	13.91	-	0.01	0.03	-	1.29
RT STA 5+037.177 TO RT STA 5+109.177	72.00	3.05 TO 1.20	153.0	38	-	153.00	-	0.06	0.34	-	14.19
RT STA 5+109.177 TO LT STA 5+242.974	133.80	1.20	160.6	38	-	160.56	-	0.07	0.35	-	14.89
RT STA 5+242.974 TO RT STA 5+314.974	72.00	1.20 TO 3.05	153.0	38	-	153.00	-	0.06	0.34	-	14.19
RT STA 5+314.974 TO RT STA 5+319.534 (RAMP)	4.56	3.05	13.9	38	-	13.91	-	0.01	0.03	-	1.29
RT STA 5+319.534 TO RT STA 5+665.395	345.86	3.05	1054.9	38	-	1,054.88	-	0.43	2.32	-	97.81
RT STA 5+691.845 TO RT STA 6+005.500	313.66	3.05	956.6	38	-	956.65	-	0.39	2.10	-	88.70
RT STA 6+005.500 TO RT STA 6+065.500	60.00	3.05 TO 1.20	127.5	38	-	127.50	-	0.05	0.28	-	11.82
RT STA 6+065.500 TO RT STA 6+129.000 (RT TURN LANE)	63.50	1.20	76.2	38	-	76.20	-	0.03	0.17	-	7.07
LAND FILL ROAD (LT & RT SHLDS)	64.42	1.20	77.3	38	-	-	77.30	0.03	0.17	-	7.17
RT STA 6+170.210 TO RT STA 6+507.888	337.68	3.05	1029.9	38	-	1,029.92	-	0.42	2.27	-	95.49
RT STA 6+507.888 TO RT STA 6+726.384 (SE CORRECTION)	218.50	3.05	666.4	38	-	666.41	-	0.27	1.47	-	61.79
RT STA 6+750.609 TO RT STA 7+039.050	288.44	3.05	879.7	38	-	879.75	-	0.36	1.94	-	81.57
RT STA 7+039.050 TO RT STA 7+303.267 (SE CORRECTION)	264.22	3.05	805.9	38	-	805.86	-	0.33	1.77	-	74.72
RT STA 7+303.267 TO RT STA 7+337.440	34.17	3.05	104.2	38	-	104.23	-	0.04	0.23	-	9.66
RT STA 7+337.440 TO RT STA 7+342.000 (RAMP)	4.56	3.05	13.9	38	-	-	13.91	0.01	0.03	-	1.29
TOTAL =					2,701.8	13,053.6	127.4	6.5	34.9		1,534.5

NOTE: SHOULDERS SHALL NOT CONTINUE THROUGH SIDE ROADS.

PLOT DATE = 4/7/2005
 FILE NAME = G:\Projects\4653898\tech\4653898.dgn
 PLOT SCALE = 1/4" = 1' / 1/4"
 USER NAME = bob

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES
SECTION : 24RS-4; 27RS-7
MONTGOMERY COUNTY

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY