

**SURFACING**

LOCATION STATION TO STATION	ROADWAY	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N70	BITUMINOUS BASE COURSE SUPERPAVE 9 1/2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	PAVEMENT REMOVAL	BITUMINOUS SURFACE REMOVAL 3/4"	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	COMMENTS
		TON	TON	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	
58+00.00 - 63+27.30	US 54	178			0.8	4.2			2124		40	US 54 MILLING AND RESURFACING
59+89.58 - 61+41.67	US 54	9	6	108	0.1	0.2						WIDENING ON NORTHEAST QUADRANT
10+19.41 - 10+60.00	GROVE ST	30			0.1	0.4				205	61	VARIABLE DEPTH MILLING AND RESURFACING
10+44.74 - 12+30.05	GROVE ST	17	11	197	0.1	0.4						WIDENING ON NORTHWEST QUADRANT
10+60.00 - 12+00.05	GROVE ST	29	20		0.1	0.7	273	350				GROVE STREET MILLING AND RESURFACING
12+00.05 - 12+30.05	GROVE ST	10			0.1	0.2				82	14	GROVE STREET BUTT JOINT
<b>TOTALS</b>		273	37	305	1.3	6.1	273	350	2124	287	115	

**ENTRANCES, PARKING LOT & PATCHING**

LOCATION STATION	ROADWAY	ENTRANCE TYPE (CE/PE/FE) OR SIDEROAD	SURFACE TYPE	(1)	(2)	MINIMUM RADIUS	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8"	AGGREGATE FOR TEMPORARY ACCESS	DRIVEWAY PAVEMENT REMOVAL	AGGREGATE BASE COURSE, TYPE B 6"	SUB-BASE GRANULAR MATERIAL TYPE A
				WIDTH	LENGTH									
				FEET	FEET	FEET	TON	TON	TON	SQ YD	TON	SQ YD	SQ YD	TON
11+07.03	GROVE ST	CE	PCC	12.0	12.0	10.0				13	3	21		
11+98.05	GROVE ST	CE	BIT	44.0	10.0	5.0	7	0.1	0.1		11	*	50	
58+51.69	US 54	CE	PCC	29.2	16.8	5.0				45	10	81		
59+03.46	US 54	CE	PCC	34.6	16.8	5.0				46	11	54		
10+90.01-10+95.87	GROVE ST OVER PR STM SWR											*		2
HARDEES PARKING LOT OVER PR STM SWR							4	0.1	0.1					13
HARDEES PARKING LOT ADDITION							6	0.1	0.1					21
<b>TOTALS</b>							17	0.3	0.3	104	35	156	50	36

NOTES

- (1) WIDTH IS MEASURED AT THE END OF THE RADIUS OF RETURN
- (2) LENGTH IS MEASURED FROM THE EDGE OF PAVEMENT
- \* PAID FOR AS PAVEMENT REMOVAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**  
SURFACING, ENTRANCES,  
PARKING LOT & PATCHING

SCALE: NONE  
DATE 12/16/03

DRAWN BY AJP  
CHECKED BY SRD