

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
321	18N	PIKE	26	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
STATE CONTRACT NO. 72691				

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING				PREFORMED PLASTIC PAVEMENT MARKING TYPE B		TEMPORARY PAVEMENT MARKING-LINE 5"	TEMPORARY PAVEMENT MARKING-LINE 24"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	SKIP DASH YELLOW LINE 5"	SOLID YELLOW LINE 5"	SOLID WHITE LINE 6"	SOLID YELLOW LINE 12"	LETTERS & SYMBOLS	SOLID WHITE LINE 24"						
	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT						
58+00.00 - 63+27.30 US 54	80	1019	115	28	117		1214		354	58	25	28
10+35.66 - 12+30.05 GROVE ST		389					389	22	164	18		
TOTALS	80	1408	115	28	117		1603	22	518	76	25	28

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE FOR 2 APPLICATIONS ON US 54 AND 3 APPLICATIONS ON GROVE STREET.

LOCATION STATION TO STATION	EARTHWORK			
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
58+00.00 - 63+27.05 US 54	200	150	50	+100
10+76.02 - 12+30.05 GROVE ST	85	65	5	+60
TOTALS	285	215	55	+160

SHRINKAGE FACTOR IS ASSUMED TO BE 25%

LOCATION STATION TO STATION	ROADWAY	PAVEMENT PATCHING, TYPE II, 10 INCH
		SQ YD
10+90.01 - 10+95.87	GROVE ST	7
TOTALS		7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
PAVEMENT MARKING, EARTHWORK
& PAVEMENT PATCHING

SCALE: NONE
DATE 12/16/03

DRAWN BY AJP
CHECKED BY SRD