

**ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES**

F.A RTE.	SECTION	COUNTY	TOTAL SHEET	SHEET NO.
1645	150RS	SANGAMON	28	3
STA.		TO STA.		
FED.ROAD DIST.NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 72876				

LOCATION OF WORK				80% FED 20% STATE			
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
PAY CODE	PAY ITEM	UNIT	TOTAL QUANTITY	1000			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPER PAVE, MIX "C", N50	TON	4,167.0	4,167.0			
X4066428	BITUMINOUS CONCRETE SURFACE COURSE, SUPER PAVE, MIX "D", N90	TON	26.0	26.0			
X4069126	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE, IL-19.0, N90 - 13"	SQ YD	230.5	230.5			
X4409400	BITUMINOUS SURFACE REMOVAL - 1 3/4"	SQ YD	37,562.0	37,562.0			
35102400	AGGREGATE BASE COURSE TYPE B 12"	SQYD	230.5	230.5			
35800100	PREPARATION OF BASE	SQYD	361.0	361.0			
40600200	BITUMINOUS MATERIAL (PRIME COAT)	TON	14.2	14.2			
40600300	AGGREGATE (PRIME COAT)	TON	74.4	74.4			
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	266.6	266.6			
40600990	TEMPORARY RAMP	SQ YD	214.0	214.0			
40800020	BITUMINOUS MATERIAL (PRIME COAT)	TON	0.1	0.1			
40800030	AGGREGATE (PRIME COAT)	TON	0.7	0.7			

* SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES