

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8027	12RS-4,TS-1	SANGAMON	31	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNITS	URBAN QUANTITY TOTAL	80% FED / 20% STATE	
				1000 QUANTITY ROADWAY	Y031-1F QUANTITY SIGNALS
X0322472	RADIUS GUARDRAIL	EACH	1	1	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX 'C'	TON	1970	1970	
X8950910	REBUILD EXISTING SIGNAL HEAD FACE, 3-SECTION, LED	EACH	6		6
X8950915	REBUILD EXISTING SIGNAL HEAD FACE, 4-SECTION, LED	EACH	2		2
X8950920	REBUILD EXISTING SIGNAL HEAD FACE, 5-SECTION, LED	EACH	2		2
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N 50	TON	70	70	
20400800	FURNISHED EXCAVATION	CU YD	13	13	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9	
40600300	AGGREGATE (PRIME COAT)	TON	47	47	
40600990	TEMPORARY RAMP	SQ YD	168	168	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	168	168	
44000006	BITUMINOUS SURFACE REMOVAL, 1.5"	SQ YD	23458	23458	
44200144	PAVEMENT PATCHING, TY II, 12"	SQ YD	50	50	
48101200	AGGREGATE SHOULDERS, TY B	TON	87	87	
63100167	TRAFFIC BARRIER TERMINAL TY I, SPECIAL (TANGENT)	EACH	7	7	
63200310	GUARDRAIL REMOVAL	FOOT	350	350	
66400505	CHAIN LINK FENCE, 8'	FOOT	300	300	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3254	3254	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	543	543	
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	25432	25432	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	90	90	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	45	45	
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LINE 6"	FOOT	280	280	
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TY B - LINE 24"	FOOT	79	79	
78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH	7	7	
88600100	DETECTOR LOOP, TY I	FOOT	712		712
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1		1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAU 8027 (TAINTOR RD.)
 SECTION 12RS-4,TS-1
 SANGAMON COUNTY
 SCALE: VERT. DRAWN BY TMJ
 HORIZ. CHECKED BY MEB
 DATE 02-14-05

PLOT DATE = 4/6/2005
 FILE NAME = c:\p\projects\72985\summary.dgn
 PLOT SCALE = 43.3735 / IN.
 REFERENCE = #REF#