

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8027	12RS-4,TS-1	SANGAMON	31	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

RESURFACING SCHEDULE			
PAY ITEM	SANGAMON AVENUE TO 8TH ST	8TH ST TO PEORIA RD	TOTALS
BITUMINOUS SURFACE REMOVAL - 1 1/2" (SQ YD)	12840	10618	23458
BITUMINOUS MATERIALS (PRIME COAT) (TONS)	5	4	9
AGGREGATE (PRIME COAT) (TONS)	26	21	47
BITUMINOUS SURFACE COURSE, SUPERPAVE, MIX "C", N50 (TONS)	1078	892	1970
AGGREGATE SHOULDERS, TY B (TONS)	63	24	87

STRIPING SCHEDULE						
LOCATION	THERMOPLASTIC				PREFORMED PLASTIC	
	5" WHITE FOOT	5" DBL YELLOW FOOT	8" WHITE FOOT	12" WHITE FOOT	6" WHITE FOOT	24" WHITE FOOT
TAINTOR ROAD						
STA 0+20 Lt to 12+00 Lt	1180					
STA 13+50 Lt to 48+00 Lt	3450					
STA 49+25 Lt to 78+50 Lt	2925					
STA 0+19 Rt to 47+60 Rt	4741					
STA 49+25 Rt to 57+60 Rt	835					
STA 58+40 Rt to 68+50 Rt	1010					
STA 69+14 Rt to 78+50 Rt	936					
STA 0+20 to 12+70		2500				
STA 13+45 to 47+60		6830				
STA 49+25 to 57+60		1670				
STA 58+40 to 78+50		4020				
TAINTOR RD & SANGAMON NE ISLAND						
			90	45		
TAINTOR RD & 8TH ST CROSSWALK						
					210	
TAINTOR RD & GATE 6 CROSSWALK						
					70	
TAINTOR RD & SANGAMON STOP BAR						
TAINTOR RD-SB LANE						
						13
SANGAMON RT TURN LANE						
						18
TAINTOR RD & BROWNING RD STOP BAR						
TAINTOR RD SB LANE						
						12
TAINTOR RD NB LANE						
						12
TAINTOR RD & 8TH ST STOP BAR						
TAINTOR RD EB LANE						
						12
TAINTOR RD WB LANE						
						12
TOTALS		25432	90	45	280	79

INCIDENTAL SURFACING SCHEDULE	
LOCATION	QUANTITY
STA 66+31 rt GATE 5 (TONS)	4.5
STA 58+02 rt GATE 6 (TONS)	19
STA 48+01 rt, STA 48+65 rt GATE 7 (TONS)	9.5
STA 68+24 lt ANIMAL PROTECTIVE LEAGUE RD (TONS)	11
STA 48+65 lt 8TH ST (TONS)	26

GUARDRAIL SCHEDULE	
TRAFFIC BARRIER TERMINAL, TY 1 SPECIAL(TANGENT)	
LOCATION	QUANTITY(EACH)
Sta 7+00 Rt	1
Sta 8+83 Lt	1
Sta 9+87 Rt	1
Sta 12+37 Lt	1
Sta 17+28 Lt	1
Sta 29+99 Lt	1
Sta 34+42 Lt	1
TOTALS	7
RADIUS GUARDRAIL	
LOCATION	QUANTITY(EACH)
Sta 15+00 Lt	1
TOTALS	1

PLOT DATE = 4/7/2005
 FILE NAME = c:\p\proj\sta\852385\sh\cover.dgn
 PLOT SCALE = 43.3725' / IN.
 REFERENCE = WIER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAU 8027 (TAINTOR RD.)
 SECTION 12RS-4,TS-1
 SANGAMON COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE: 02-14-05
 DRAWN BY: TMJ
 CHECKED BY: MEB