

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	(2,2)N	LAWRENCE	38	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-1A 90% FED 10% STATE	Y031-1F 90% FED 10% STATE
20200100	EARTH EXCAVATION	CU YD	755	755	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	95	95	
20400800	FURNISHED EXCAVATION	CU YD	1515	1515	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.8	0.8	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80	80	
28000300	TEMPORARY DITCH CHECKS	EACH	11	11	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
30200650	PROCESSING MODIFIED SOILS 12"	SQ YD	3875	3875	
30201800	SLAG-MODIFIED PORTLAND CEMENT	TON	39.1	39.1	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	252	252	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	904	904	
40600300	AGGREGATE (PRIME COAT)	TON	19	19	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	180	180	
40600990	TEMPORARY RAMP	SQ YD	30	30	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	4569	4569	
44000100	PAVEMENT REMOVAL	SQ YD	785	785	
44004250	PAVED SHOULDER REMOVAL	SQ YD	873	873	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	306	306	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	53	53	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	816	816	
48202410	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	SQ YD	863	863	
50104400	CONCRETE HEADWALL REMOVAL	EACH	3	3	
54201279	PIPE CULVERTS, TYPE 2 RCCP 24"	FOOT	32	32	
54201291	PIPE CULVERTS, TYPE 2 RCCP 36"	FOOT	38	38	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2	
54248510	CONCRETE COLLAR	CU YD	1.7	1.7	
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	24	24	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	29.5	29.5	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	153	153	
60621600	CONCRETE MEDIAN, TYPE SM	SQ FT	146	146	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000-1A 90% FED 10% STATE	Y031-1F 90% FED 10% STATE
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	385	385	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9366	9366	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	477	477	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	513	513	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	60	60	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	64	64	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9366	9366	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	477	477	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	513	513	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	60	60	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	87	87	
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	1		1
* 80801500	WOOD POLE, 25 FT., CLASS 5	EACH	1		1
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1592		1592
* 81021540	CONDUIT, AUGERED 1 1/2" DIA., PVC	FOOT	292		292
* 81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA., GALVANIZED STEEL	FOOT	72		72
* 81400100	HANDHOLE	EACH	3		3
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1498		1498
* 85800100	FLASHER CONTROLLER	EACH	1		1

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY: \_\_\_\_\_ CHECKED BY: \_\_\_\_\_

teasleyck 3/31/2005 c:\projects\74035d\02004.psdgn



PLOT DATE: 3/31/2005  
 PLOT SCALE: 1"=100'  
 REFERENCE: \*BREF\*