

stef femmk
 3/29/2005
 c:\projects\74073d\05404pa.dgn
 GEN

CONTRACT NO. 74073

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	*	JEFFERSON	10	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D-7 JOINT REPAIRS 2005-1

GENERAL NOTES

This section shall be constructed in accordance with the plans; the STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, adopted January 1, 2002; the SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, adopted January 1, 2005; and the SPECIAL PROVISIONS included in the proposal.

This project is located south of Mt. Vernon on IL. Route 148 in Jefferson County. The project includes the following structure: Structure Number 041-0096 over the Big Muddy River.

The work included in this project consists of the removal and replacement of the existing neoprene expansion joints, pavement striping, and all other work necessary to complete this section.

The reflective lenses of all raised reflective markers located between the stop bars and the end of the approach pavements shall be removed prior to stage 1 construction. This work will be paid for at the contract unit price for RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL. Replacement of the bi-directional amber reflectors at the completion of stage 2 will be paid for at the contract unit price for REPLACEMENT REFLECTOR.

The quantities of paint pavement marking line were computed as follows:

144	Feet (yellow)
1798	Feet (white)
1942	Feet (Total)

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVERSHEET
2	GENERAL NOTES & INDEX OF SHEETS
3	SUMMARY OF QUANTITY
4	QUANTITY SCHEDULES
5	GENERAL PLAN AND ELEVATION
6	STAGE CONSTRUCTION DETAILS
7-8	EXPANSION JOINT DETAILS
9	NEOPRENE EXPANSION JOINTS
10	BAR SPLICER ASSEMBLY DETAIL

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 10:

000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
701006-02	OFF-ROAD OPERATIONS, 2L 2W, 15' TO 24" AWAY, SPEEDS > 45 MPH
701011-01	OFF-ROAD MOVING OPERATIONS, 2L 2W, DAY ONLY, FOR SPEEDS > 45 MPH
701201-02	LANE CLOSURE, 2L 2W, DAY ONLY, ON-ROAD TO 600 MM OFF-ROAD, SPEEDS > 45 MPH
701301-02	LANE CLOSURE, 2L 2W, SHORT TIME OPERATIONS
701311-02	LANE CLOSURE, 2L 2W, MOVING DAY ONLY OPERATIONS
701316-03	LANE CLOSURE, 2L 2W, BRIDGE REPAIR, FOR SPEEDS > 45 MPH
701326-02	LANE CLOSURE, 2L 2W, PAVEMENT WIDENING, FOR SPEEDS > 45 MPH
702001-05	TRAFFIC CONTROL DEVICES
720001	SIGN PANEL MOUNTING DETAILS
720006	SIGN PANEL ERECTION DETAILS
780001-01	TYPICAL PAVEMENT MARKINGS
781001-02	TYPICAL APPLICATIONS OF RAISED REFLECTIVE PAVEMENT MARKERS
886001	DETECTOR LOOP INSTALLATIONS
886006	TYPICAL LAYOUT FOR DETECTION LOOPS

PLOT DATE = 3/29/2005
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 REFERENCE = #REF#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

SCALE: VERT.
 DATE: HORIZ.

DRAWN BY
 CHECKED BY