

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
726	*	JEFFERSON	10	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D-7 JOINT REPAIRS 2005-1

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SFTY-2A		
50102400	CONCRETE REMOVAL	CU YD	34.1	34.1		
50300155	NEOPRENE EXPANSION JOINT 2 1/2"	FOOT	68	68		
50300160	NEOPRENE EXPANSION JOINT 4"	FOOT	34	34		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	34.3	34.3		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6296	6296		
51500200	RELOCATING NAME PLATES	EACH	1	1		
67100100	MOBILIZATION	L SUM	1	1		
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	57	57		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5940	5940		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1386	1386		
*78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1942	1942		
*78100300	REPLACEMENT REFLECTOR	EACH	8	8		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	637	637		
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	8	8		
Z0002600	BAR SPLICERS	EACH	40	40		

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE


ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY _____
CHECKED BY _____

steffenmk
 3/29/2005
 c:\projects\74073\d05404pa.dgn


PLOT DATE * 3/29/2005
 FILE NAME * #FILE#
 PLOT SCALE * #SCALE#
 REFERENCE * #REF#