FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
64	82-9RA-I-2	ST. CLAIR	4	2
STA.		TO STA.		
CONTRACT NO.: 76895				

PLAN	SURVEYED	BY	DATE
	PLOTTED		
	ALIGNMENT CHECKED		
NOTE BOOK NO.	DTM MAY CHECKED		
	CADD FILE NAME		

INDEX OF SHEETS

1 COVER SHEET

2 INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS

3 SUMMARY OF QUANTITIES

4 INFLUENT & CONTROL STRUCTURE DETAILS

HIGHWAY STANDARDS

702001-05

GENERAL NOTES

1. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:

   - CLINTON COUNTY ELECTRIC COOPERATIVE (ELECTRIC)
   - VILLAGE OF NEW BADEN (WATER)
   - VERIZON NORTH, INC. (COMMUNICATIONS)

   (MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY •. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)

2. THE CONTRACTOR IS RESPONSIBLE FOR LOWERING THE LAGOONS BELOW THE DISCHARGE PIPES.

3. THE CONTRACTOR WILL NOT BE ABLE TO DISCHARGE LAGOONS INTO THE CREEK.

4. ALL BOLTS AND MATERIALS MUST BE STAINLESS STEEL.

5. THE REST AREAS WILL NEED TO BE CLOSED DURING REPLACEMENT OF VALVES. THIS CLOSURE MUST BE APPROVED BY THE DEPARTMENT.

6. THE CONTRACTOR MUST NOTIFY THE RESIDENT OF THE START DATE SO PROPER NOTIFICATION, SIGNING AND A PRESS RELEASE CAN BE COORDINATED FOR THE CLOSURE. THE PRESS RELEASE MUST BE ISSUED 5 DAYS BEFORE WORK IS TO BEGIN. ONCE WORK BEGINS IT MUST BE COMPLETED WITHIN 10 CONSECUTIVE CALENDAR DAYS. THE 10 CONSECUTIVE CALENDAR DAYS CAN NOT INCLUDE ANY LEGAL HOLIDAYS. THE LEGAL HOLIDAYS ARE LABOR DAY, THANKSGIVING DAY AND CHRISTMAS DAY. SEE SPECIAL PROVISIONS FOR THE PENALTY IF THE CONTRACTOR IS UNABLE TO COMPLETE THE WORK DURING THE ALLOTTED TIME.

7. RESIDENT SHALL CONTACT:

   JEFF ABEL DISTRICT OFFICE (618) 346-3283 (SIGNS)

   STEVE WHEELER WOOD RIVER MAINTENANCE YARD (618) 259-1440 (NOTIFICATION)

8. THE CONTRACTOR SHALL HAVE ALL MATERIALS ON HAND BEFORE WORK BEGINS. MATERIALS MUST BE APPROVED BY THE DEPARTMENT.

9. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.

10. WHERE SECTION OR SUB SECTION MONUMENTS ARE ENCOUNTERED THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE DISTURBED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THE LOCATION.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, GENERAL NOTES AND HIGHWAY STANDARDS

FAI ROUTE 64
SECTION 82-9RA-I-2
ST. CLAIR COUNTY

DRAWN BY:

PLOT DATE: 3/31/2005

$$$$DATE$$
3/31/2005
c:\pwworkspace\projects\ed23\d05\plan\pi\d23d05a.dgn
$$$$USER$$
$$$$REF:
$$$$REF: