

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	3
STA. 10+70.70		TO STA. 66+16.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 83781				

**FAU RTE 2652 - SOUTH VILLA AVENUE
FROM ROOSEVELT ROAD TO MADISON STREET
SECTION 00-00069-00-PV**

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	H23 ROADWAY 1000-2A	Q40 SIDEWALK 1000-1B	H23 LIGHTING Y030-1E	PARTICIPATING QUANTITY		O7C NON-PART. QUANTITY
							STP QUANTITY	CMAQ QUANTITY	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	120	120			120		Y060
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	85	85			85		
20101000	TEMPORARY FENCE	FOOT	615	615			615		
20101100	TREE TRUNK PROTECTION	EACH	41	41			41		
20200100	EARTH EXCAVATION	CU YD	3,946	3,946			3,946		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,425	1,425			1,425		
20700220	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	4,239	4,239			4,239		
20800150	TRENCH BACKFILL	CU YD	6,227	4827			4,827		1,400
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	14,969	14,969			14,969		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	186	186			186		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	186	186			186		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	186	186			186		
25200110	SODDING, SALT TOLERANT	SQ YD	14,969	14,969			14,969		
25200200	SUPPLEMENTAL WATERING	UNIT	675	675			675		
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	3.1	3.1			3.1		
28000400	PERIMETER EROSION BARRIER	FOOT	6,570	6570			6,570		
28000510	INLET FILTERS	EACH	153	153			153		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	913	913			913		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	5,841	5841			5,841		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	527	527			527		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	960	960			960		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	52,570		52,570			52,570	
44000100	PAVEMENT REMOVAL	SQ YD	19,489	19,489			19,489		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3,619	3,619			3,619		
44000300	CURB REMOVAL	FOOT	58	58			58		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,857	3,857			3,857		
44000600	SIDEWALK REMOVAL	SQ FT	15,089		15,089			15,089	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	200	200			200		
50105220	PIPE CULVERT REMOVAL	FOOT	878	878			878		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	16	16			16		
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	100	100			100		

DATE	BY	SURVEYED	ALIGNED	CHECKED	BY	DATE
PLAN	NO.	NOTE BOOK	NO.	FILE NAME		

DATE	BY	SURVEYED	GRADES	CHECKED	BY	DATE
PROFILE	NO.	NOTE BOOK	NO.	FILE NAME		

REVISIONS	
NAME	DATE



VILLAGE OF VILLA PARK, ILLINOIS

**SOUTH VILLA AVENUE
SUMMARY OF QUANTITIES
SHEET 1 OF 5**

SCALE: NONE
DATE: 11-NOV-2004

DRAWN BY: E.D.
CHECKED BY: J.T.G.