

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2652	00-00069-00-PV	DUPAGE	146	6
STA. 10+70.70		TO STA. 66+16.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 83781				

**FAU RTE 2652 - SOUTH VILLA AVENUE  
FROM ROOSEVELT ROAD TO MADISON STREET  
SECTION 00-00069-00-PV**

**SUMMARY OF QUANTITIES**

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	H23 ROADWAY 1000-2A	Q40 SIDEWALK 1000-1B	H23 LIGHTING Y030-1E	PARTICIPATING QUANTITY		OTC NON-PART. QUANTITY
							STP QUANTITY	CMAQ QUANTITY	
81600320	UNIT DUCT, WITH 2-1/C NO. 6 AND 1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 1" DIA., POLYETHYLENE	FOOT	1,535			1,535	1,535		Y060
81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	224			224	224		
82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	48			48	48		
82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240VOLT	EACH	2			2	2		
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	408			408	408		
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	6			6	6		
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	153	153			153		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	99	99			99		
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	40	40			40		
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	11	11			11		
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	38	38			38		
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	54	54			54		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3,013	3013			3,013		
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	43	43			43		
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	70	70			70		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	23	23			23		
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	160	160			160		
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	210	210			210		
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	199	199			199		
550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	181	181			181		
A2000920	TREE, ACER MIYABEI MORTON (STATE STREET MIYABEI MAPLE) 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	10	10			10		
A2001416	TREE, ACER SACCHARINUM AUTUMN BLAZE (AUTUMN BLAZE SILVER MAPLE) 2" CALIPER, BALLED AND BURLAPPED	EACH	10	10			10		
B2004516	TREE, MALUS RED JEWEL (RED JEWEL CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	20	20			20		
X0300558	SANITARY SEWER REMOVAL AND REPLACEMENT 8"	FOOT	40						40
X0301892	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1			1		
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS), 12 INCH	FOOT	673	673			673		
X0322468	GAS VALVE TO BE ADJUSTED	EACH	1	1			1		
X0323353	GATE VALVES 10"	EACH	5						5
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	153	153			153		
X0712400	TEMPORARY PAVEMENT	SQ YD	285	285			285		

DATE	BY
DATE	BY
DATE	BY
DATE	BY
DATE	BY
DATE	BY

DATE	BY
DATE	BY
DATE	BY
DATE	BY
DATE	BY
DATE	BY

REVISIONS	
NAME	DATE



VILLAGE OF VILLA PARK, ILLINOIS

**SOUTH VILLA AVENUE  
SUMMARY OF QUANTITIES  
SHEET 4 OF 5**

SCALE: NONE      DRAWN BY: E.D.  
DATE: 11-NOV-2004      CHECKED BY: J.T.G.